

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
373	0707-608 HB-I-4	COOK	40	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CONTRACT NO. 60C94

CODE NO.	ITEM	UNIT	TOTAL QUANTITIES 100% STATE	CONSTRUCTION TYPE CODE										
				S.N. 016-0485 FUNDS	S.N. 016-0486 FUNDS	S.N. 016-0487 FUNDS	S.N. 016-0488 FUNDS	S.N. 016-0489 FUNDS	S.N. 016-1001 FUNDS	S.N. 016-1026 FUNDS	S.N. 016-2454 FUNDS	S.N. 016-2455 FUNDS	S.N. 016-2456 FUNDS	S.N. 016-2457 FUNDS
				SFTY-2A	SFTY-2A	SFTY-2A	SFTY-2A	SFTY-2A	SFTY-2A	SFTY-2A	SFTY-2A	SFTY-2A	SFTY-2A	SFTY-2A
50102400	CONCRETE REMOVAL	CU YD	15.5								11.0			4.5
50157301	PROTECTIVE SHIELD (PERMANENT)	SQ YD	3,395					315			1,540	1,540		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	15.5							11.0				4.5
50300260	BRIDGE DECK GROOVING	SQ YD	367			281		86						
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3070							2080				990
50800515	BAR SPLICERS	EACH	32							32				
52000110	PREFORMED JOINT STRIP SEAL	FOOT	107							75				32
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	0.6	0.6	0.6	0.6	0.6		0.6	0.6	0.6	0.6	0.6
67100100	MOBILIZATION	L SUM	1	0.1	0.1	0.1	0.1	0.1		0.1	0.1	0.1	0.1	0.1
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	0.1	0.1	0.1	0.1	0.1		0.1	0.1	0.1	0.1	0.1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	30	3	3	3	3	3		3	3	3	3	3
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	8					4				4	0	
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	2,000	200	200	200	200	200		200	200	200	200	200
* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	3,000	300	300	300	300	300		300	300	300	300	300
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	80	8	8	8	8	8		8	8	8	8	8
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	80	8	8	8	8	8		8	8	8	8	8
X0322489	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/2 INCHES	SQ YD	367			281		86						
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	2,400		400	1000		1000						
Z0006225	BRIDGE DECK HYDRO-SCARIFICATION 2 1/2"	SQ YD	367			281		86						
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	327	147	13	83					15	28	8	33
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	114		6	1	2	3	3		7	62	9	21
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1				0.25	0.25			0.25	0.25		

* SPECIALTY ITEM

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
IL. RTE. 171

REVISIONS	
NAME	DATE

SCALE: NONE
DATE: DECEMBER 8, 2008
DRAWN BY: S.J.P./A.C.S.
CHECKED BY: S.J.P./A.C.S.
CHRISTIAN-ROGE & ASSOC., INC.
CHICAGO ILLINOIS

Rev. 2-23-09

Rev.