

## NOTES:

- 1. USE BLACK LETTERING ON ORANGE BACKGROUND.
- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN (1) WITH INSTALLED PANEL (2) ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL (2) SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
- 7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

FILE NAME	4E =	USER NAME = geglænobt	DESIGNED -	REVISED - R. MIRS 09-15-97		ARTERIAL ROAD						F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET S NO.
W:\diststd	W:\diststd\22x34\to22.dgn		DRAWN	REVISED - R. MIRS 12-11-97	STATE OF ILLINOIS	INFORMATION SIGN			M CICNI		345	2008-073 GRR	COOK/KANE	20	20	
1		PLOT SCALE = 50.000 '/ IN.	CHECKED -	REVISED -T. RAMMACHER 02-02-99	DEPARTMENT OF TRANSPORTATION				MITURINATION SIGN				TC-22	CONTRACT	T NO.	60F74
		PLOT DATE = 1/4/2008	DATE -	REVISED - C. JUCIUS 01-31-07	SC/	SCALE: NONE	SHEET NO.	. 1 OF 1	SHEETS	STA.	TO STA,	FED. RO/	AD DIST. NO. 1 ILLINOIS FED. A	ID PROJECT		