



CONSTRUCTION NOTE:
 ① EXISTING INTERCONNECT CONDUIT AND SYSTEM HANDHOLES SHOWN ARE TO BE UTILIZED FOR PERMANENT INTERCONNECT.

RESTORATION OF WORK AREA. RESTORATION OF THE TRAFFIC SIGNAL WORK AREA SHALL BE INCIDENTAL TO THE RELATED PAY ITEM SUCH AS FOUNDATION, CONDUIT, HANDHOLE, TRENCH AND BACKFILL, ETC., AND NO EXTRA COMPENSATION SHALL BE ALLOWED. ALL ROADWAY SURFACES SUCH AS SHOULDERS, MEDIANS, SIDEWALKS, PAVEMENT, ETC. SHALL BE REPLACED IN KIND. ALL DAMAGE TO MOWED LAWNS SHALL BE REPLACED WITH AN APPROVED SOD, AND ALL DAMAGE TO UNMOWED FIELDS SHALL BE SEEDED IN ACCORDANCE WITH STANDARD SPECIFICATIONS 252 AND 250 RESPECTIVELY.

TEMPORARY INTERCONNECT PLAN LEGEND

- CONTROLLER
- SERVICE INSTALLATION
- EXISTING HANDHOLE
- EXISTING CONDUIT
- AERIAL INTERCONNECT CABLE - 3 PAIR #18
- WOOD POLE CLASS 4 30 FT. MINIMUM
- SYSTEM
- EXISTING INTERSECTION

DATE	BY	DATE	BY
PLAN	DATE	DATE	BY
NO.			
NO.			

CHRISTOPHER B. BURKE ENGINEERING LTD.
 3515 West Higgins Road, Suite 600
 Rosemead, Illinois 60018
 (917) 822-0500

FILE NAME =	USER NAME = FPACTIONE	DESIGNED - ABR	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	TEMPORARY INTERCONNECT PLAN				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
N:\dot\0808040\Task G-P IL 50\Traffic\INT2-temp_IL50.dgn	DRAWN - FPB	REVISED -			IL. ROUTE 50 (CICERO AVE.) FROM 39th ST. (PERSHING RD.) TO ROOSEVELT RD.	350	2008-080-1	COOK	76	53			
PLOT SCALE = 50'	CHECKED - MJT	REVISED -			CICERO, ILLINOIS	CONTRACT NO. 60F82							
PLOT DATE = 12/10/2008	DATE -	REVISED -			SCALE: 1"= 50'	SHEET NO.	OF SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT		