

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
333	2002-101N	LAKE	75	4
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		ROADWAY I000-2A				
66400105	CHAIN LINK FENCE, 4'	FOOT	310	310				
66410300	CHAIN LINK FENCE REMOVAL	FOOT	310	310				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8				
67100100	MOBILIZATION	L SUM	1	1				
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5100	5100				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	285	285				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	19026	19026				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	935	935				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	220	220				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	70	70				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	285	285				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	19026	19026				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	935	935				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	220	220				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	70	70				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	220	220				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	190	190				
A2006616	TREE, QUERCUS IMBRICARIA (SHINGLE OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	8	8				
* A2007916	TREE, TILIA AMERICANA REDMOND (REDMOND AMERICAN LINDEN), 2" CALIPER, BALLED AND BURLAPPED	EACH	12	12				
* B2002716	TREE, MALUS ADIRONDACK (ADIRONDACK CRAB APPLE), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	8	8				

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		ROADWAY I000-2A				
B2005413	TREE, PRUNUS VIRGINIANA SCHUBERT (CANADA RED CHOKECHERRY), 1-3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	5	5				
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	103	103				
X0322672	SPLIT RAIL FENCE TO BE REMOVED AND RE-ERECTED	FOOT	180	180				
X0914000	PRECAST CONCRETE BOX CULVERT END SECTIONS 2' X 2'	EACH	2	2				
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	4	4				
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	4	4				
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	948	948				
XX006846	AGGREGATE FIELD ENTRANCE	SQ YD	72	72				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1				
MP Z0014800	CULVERT TO BE CLEANED	FOOT	153	153				
⊙ Z0076600	TRAINEES	HOUR	500	500				
X0325936	SOLAR POWERED FLASHER/ POST MOUNTED (YELLOW LED DISPLAY)	EACH	1	1				
* A2005016	TREE, SYMNOCLADUS DIDICUS (KENTUCKY COFFEE TREE), 2" CALIPER, BALLED AND BURLAPPED	EACH	8	8				
* B2000646	TREE, AMELANCHIER X. GRANDIFLORA (APPLE SERVICEBERRY), 6' HEIGHT, SHRUB FORM, BALLED AND BURLAPPED	EACH	5	5				
* X0325714	POST MOUNTED FLASHING BEACON, SOLAR POWERED INSTALLATION	EACH	1	1				

* Specialty Items
 ⊙ Y080
 NP = Non-participating

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 FAP 333 - IL 120 (AT BACON ROAD & AT CEDAR LAKE ROAD)

Rev.