

CONTRACT NO. 62710

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		BRIDGE X028-2A				
20200100	EARTH EXCAVATION	CU YD	90	90				
20201006	GRADING AND SHAPING SHOULDERS	UNIT	8	8				
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	214	214				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	700	700				
25000210	SEEDING, CLASS 2A	ACRE	0.1	0.1				
25000314	SEEDING, CLASS 4B	ACRE	0.1	0.1				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	15	15				
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	15	15				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	15	15				
25100630	EROSION CONTROL BLANKET	SO YD	700	700				
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	15	15				
28000300	TEMPORARY DITCH CHECKS	EACH	4	4				
28000400	PERIMETER EROSION BARRIER	FOOT	835	835				
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SO YD	930	930				
35300410	PORTLAND CEMENT CONCRETE BASE COURSE 9 1/2"	SO YD	260	260				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1	1				
40600300	AGGREGATE (PRIME COAT)	TON	5	5				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	1	1				
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	60	60				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	25	25				
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	90	90				
44000100	PAVEMENT REMOVAL	SO YD	430	430				
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	815	815				
44004250	PAVED SHOULDER REMOVAL	SO YD	135	135				
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1200	1200				
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SO YD	250	250				
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SO YD	310	310				

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		BRIDGE X028-2A				
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1				
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	8921	8921				
50800105	REINFORCEMENT BARS	POUND	37710	37710				
50800515	BAR SPLICERS	EACH	232	232				
51205200	TEMPORARY SHEET PILING	SO FT	956	956				
51500100	NAME PLATES	EACH	1	1				
54003000	CONCRETE BOX CULVERTS	CU YD	160.8	160.8				
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	100	100				
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4				
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	1				
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1				
70106700	TEMPORARY RUMBLE STRIP	EACH	6	6				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	700	700				
70400100	TEMPORARY CONCRETE BARRIER	FOOT	420	420				
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	420	420				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	900	900				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	5	5				
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	5	5				
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4				
X0323817	SEDIMENT CONTROL, SILT CURTAIN	EACH	2	2				
50900200	STEEL RAILING, TYPE 2399	FOOT	76	76				
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	1850	1850				
X0325841	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 24 INCH	FOOT	48	48				
X0712400	TEMPORARY PAVEMENT	SO YD	480	480				

12/23/2008 10:00:00 AM C:\P\1001\1001\1001.dwg

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

*Specialty Items