

SUMMARY OF QUANTITIES

SPECIALTY ITEM	CODE NO	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	STU	ITEP	STU				
					70% FED 30% STATE	80% FED 20% VILLAGE	100% VILLAGE	HARTS	TOUHY	WAUKEGAN	ECT
					I000-2A	Y003	Y060	70% FED 30% STATE Y031-1F	70% FED 30% STATE Y031-1F	70% FED 30% STATE Y031-1F	70% FED 30% STATE Y031-1F
	60266500	VALVE VAULTS TO BE REMOVED	EACH	2			2				
	60404700	FRAMES AND GRATES, TYPE 10	EACH	4	4						
	60404800	FRAMES AND GRATES, TYPE 11	EACH	20	20						
	60405740	FRAME AND GRATE TO BE REMOVED	EACH	20	20						
	60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	8	8						
	60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	49	49						
	60604200	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.12 (SPECIAL)	FOOT	14,300	14,300						
	60624600	CORRUGATED MEDIAN	SQ FT	3,600	3,600						
★	66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	730	730						
★	66900400	SPECIAL WASTE GROUND WATER DISPOSAL	GAL	20,000	20,000						
★	66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1						
★	66900530	SOIL DISPOSAL ANALYSIS	EACH	7	7						
★	66901000	BACKFILL PLUGS	CU YD	140	140						
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	13	13						
	67100100	MOBILIZATION	L SUM	1	1						
	70101800	TRAFFIC CONTROL & PROTECTION, (SPECIAL)	L SUM	1	1						
	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	24	24						
	70300210	TEMPORARY PAVEMENT MARKING, LETTERS & SYMBOLS	SQ FT	729	729						
	70300220	TEMPORARY PAVEMENT MARKING, LINE 4"	FOOT	30,434	30,434						
	70300240	TEMPORARY PAVEMENT MARKING, LINE 6"	FOOT	156	156						
	70300260	TEMPORARY PAVEMENT MARKING, LINE 12"	FOOT	231	231						
	70300510	PAVEMENT MARKING TAPE, TYPE III, LETTERS & SYMBOLS	SQ FT	328	328						
	70300520	PAVEMENT MARKING TAPE, TYPE III, LINE 4"	FOOT	6,440	6,440						
	70300540	PAVEMENT MARKING TAPE, TYPE III, LINE 6"	FOOT	1,474	1,474						
	70300570	PAVEMENT MARKING TAPE, TYPE III, LINE 24"	FOOT	1,474	1,474						
	72400710	RELOCATE SIGN PANEL, TYPE I	SQ FT	73	73						
	72900100	METAL POST, TYPE A	FOOT	154	154						
★	78000100	THERMOPLASTIC PAVEMENT MARKING, LETTERS & SYMBOLS	SQ FT	37	37						
★	78000200	THERMOPLASTIC PAVEMENT MARKING, LINE 4"	FOOT	17,243	17,243						
★	78000400	THERMOPLASTIC PAVEMENT MARKING, LINE 6"	FOOT	697	697						
★	78000600	THERMOPLASTIC PAVEMENT MARKING, LINE 12"	FOOT	150	150						
★	78000650	THERMOPLASTIC PAVEMENT MARKING, LINE 24"	FOOT	128	128						
★	78008200	POLYUREA PAVEMENT MARKING, TYPE I, LETTERS & SYMBOLS	SQ FT	255	255						
★	78008210	POLYUREA PAVEMENT MARKING, TYPE I, LINE 4"	FOOT	5,947	5,947						
★	78008230	POLYUREA PAVEMENT MARKING, TYPE I, LINE 6"	FOOT	1,718	1,718						
★	78008270	POLYUREA PAVEMENT MARKING, TYPE I, LINE 24"	FOOT	323	323						
★	78100100	RAISED REFLECTIVE PAVEMENT MARKERS	EACH	330	330						
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	29,996	29,996						
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	330	330						
★	80400100	ELECTRIC SERVICE INSTALLATION	EACH	1			1				
★	80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1			1				
★	81000600	CONDUIT IN TRENCH, 2" DIA, GALVANIZED STEEL	FOOT	1,624				522			1,102
★	81000700	CONDUIT IN TRENCH, 2.5" DIA, GALVANIZED STEEL	FOOT	93				66		27	
★	81000800	CONDUIT IN TRENCH, 3" DIA, GALVANIZED STEEL	FOOT	147			120	27			
★	81018500	CONDUIT PUSHED, 2" DIA, GALVANIZED STEEL	FOOT	27				27			
★	81018600	CONDUIT PUSHED, 2.5" DIA, GALVANIZED STEEL	FOOT	143				143			
★	81018900	CONDUIT PUSHED, 4" DIA, GALVANIZED STEEL	FOOT	321			264	57			
★	81400100	HANDHOLE	EACH	5				4			1
★	81400200	HEAVY-DUTY HANDHOLE	EACH	1				1			
★	81400300	DOUBLE HANDHOLE	EACH	2				2			
★	81702460	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 3/0	FOOT	300			300				
★	81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	2,248			500	631		23	1,094
★	82102310	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 310 WATT	EACH	8			8				
★	82500505	LIGHTING CONTROLLER, SPECIAL	EACH	1			1				



USER NAME = charlke	DESIGNED - JPA	REVISED -
PLOT SCALE = N.T.S.	DRAWN - JPA	REVISED -
PLOT DATE = 1/16/2009	CHECKED - JLP	REVISED -
	DATE - 12/16/08	REVISED -

VILLAGE OF NILES

SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET NO. 2 OF 3 SHEETS STA. TO STA.

F.A.U. RTE. 3513	SECTION 08-00107-01-PV	COUNTY COOK	TOTAL SHEETS 169	SHEET NO. 5
FED. ROAD DIST. NO. ILLINOIS		FED. AID PROJECT M -8003(723)	CONTRACT NO.	