

P. A. U. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
4304	04-00045-00-FP	WILL	033	002
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT #63108

SUMMARY OF QUANTITIES					PAVEMENT	MARKINGS	SIGNS	LANDSCAPE	LOCAL AGENCY
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	CONSTRUCTION TYPE CODE				
					1000-2A	SFTY-1D	Y002-1C	Y003	VILLAGE OF PEOTONE
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	18	18				
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	7	7				
	20200100	EARTH EXCAVATION	CU YD	7780	7780				
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	100	100				
	20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	100	100				
	20800150	TRENCH BACKFILL	CU YD	1351	1351				
	21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	3620	3620				
	21300010	EXPLORATION TRENCH, SPECIAL	FOOT	60	60				
	25200650	SODDING, SALT TOLERANT (SPECIAL)	SQ YD	3620	3620				
	28000400	PERIMETER EROSION BARRIER	FOOT	2700	2700				
	28000510	INLET FILTERS	EACH	29	29				
	28100101	STONE RIPRAP, CLASS A1	SQ YD	25	25				
	35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	510	510				
	40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	850	850				
	40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1305	1305				
	40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	70	70				
	40701861	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9"	SQ YD	13035	13035				
	42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	250	250				
	42400430	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH, SPECIAL	SQ FT	19630	19630				
	42400800	DETECTABLE WARNINGS	SQ FT	240	240				
	44000100	PAVEMENT REMOVAL	SQ YD	8700	8700				
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1400	1400				
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2290	2290				
	44000600	SIDEWALK REMOVAL	SQ FT	2355	2355				
	48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	122	122				
	50105210	REMOVE EXISTING CULVERTS	FOOT	30	30				
	54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1	1				
	54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1				
	550A0030	STORM SEWERS, CLASS A, TYPE 1 8"	FOOT	391	391				
	550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	173	173				
	550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	104	104				
	550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	208	208				
	550A0110	STORM SEWERS, CLASS A, TYPE 1 21"	FOOT	74	74				
	550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	461	461				
	550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	305	305				
	550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	75	75				
	55100300	STORM SEWER REMOVAL 8"	FOOT	37	37				
	55100400	STORM SEWER REMOVAL 10"	FOOT	14	14				
	55100500	STORM SEWER REMOVAL 12"	FOOT	15	15				
	55100700	STORM SEWER REMOVAL 15"	FOOT	30	30				
*	56103100	DUCTILE IRON WATER MAIN 8"	FOOT	255					255
*	56103200	DUCTILE IRON WATER MAIN 10"	FOOT	65					65
*	56103300	DUCTILE IRON WATER MAIN, 12"	FOOT	2335					2335
*	56106500	ADJUSTING WATER MAIN 10"	FOOT	30					30
*	56108800	TAPPING VALVES AND SLEEVES 6"	EACH	4					4
*	56109000	TAPPING VALVES AND SLEEVES 10"	EACH	4					4
*	56400500	FIRE HYDRANTS TO BE REMOVED	EACH	5					5
*	56400820	FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	EACH	9					9

* - INDICATES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**RATHJE ROAD
ROAD RECONSTRUCTION
SUMMARY OF QUANTITIES**

SCALE: VERT. NA
HORIZ. NA
DATE 09-18-09

DRAWN BY AG
CHECKED BY HLG