

F. A. U. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
4304	04-00045-00-PP	WILL	033	003
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CONTRACT #63108

SUMMARY OF QUANTITIES					PAVEMENT	MARKINGS	SIGNS	LANDSCAPE	LOCAL AGENCY
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	CONSTRUCTION TYPE CODE				
					1000-2A	SFTY-1D	Y002-1C	Y003	VILLAGE OF PEOTONE
	60107600	PIPE UNDERDRAINS 4"	FOOT	400	400				
	60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1				
	60201105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 11 FRAME AND GRATE	EACH	15	15				
	60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	9	9				
	60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3				
	60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	7	7				
	60236800	INLETS, TYPE A, TYPE 11 FRAME AND GRATE	EACH	6	6				
	60248700	VALVE VAULTS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1					1
	60248900	VALVE VAULTS, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	9					9
	60249400	VALVE BOXES 6"	EACH	3					3
	60249600	VALVE BOXES 10"	EACH	3					3
	60250400	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1	1				
	60255500	MANHOLES TO BE ADJUSTED	EACH	6	6				
	60255700	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1	1				
	60266600	VALVE BOXES TO BE ADJUSTED	EACH	3					3
	60500050	REMOVING CATCH BASINS	EACH	3	3				
	60500060	REMOVING INLETS	EACH	2	2				
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	5610	5610				
	67100100	MOBILIZATION	L SUM	1	1				
	70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1				
	72000100	SIGN PANEL - TYPE 1	SQ FT	63	63				
	72900200	METAL POST - TYPE B	FOOT	130	130				
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	11025		11025			
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	725		725			
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1000		1000			
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	155		155			
	Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	15163	15163				
△	Z0076600	TRAINEES	HOUR	1000	1000				
	XX000610	RELOCATE EXISTING MAILBOX	EACH	36	36				
*	XX000679	CUT AND CAP EXISTING WATER MAIN	EACH	8					8
*	XX002907	WATER SERVICE CONNECTION (SHORT)	EACH	21					21
*	XX006814	WATER SERVICE CONNECTION (LONG)	EACH	23					23
*	XX003032	GATE VALVES, 12"	EACH	8					8
*	XX003037	DUCTILE IRON FITTINGS AND ACCESSORIES	POUND	8850					8850
	XX005369	TRAFFIC CONTROL & PROTECTION FOR TEMPORARY DETOUR	L SUM	1	1				
*	XX000836	PRESSURE TESTING AND DISINFECTION	L SUM	1					1
	X0322033	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	256	256				
	X0322034	STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH	FOOT	51	51				
	X0322035	STORM SEWER (WATER MAIN REQUIREMENTS) 18 INCH	FOOT	184	184				
	X0322125	STORM SEWER (WATER MAIN REQUIREMENTS) 24 INCH	FOOT	580	580				
*	XX001776	REMOVE AND ABANDON VALVE BOX	EACH	8					8

△ Y080

* - INDICATES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

RATHJE ROAD
ROAD RECONSTRUCTION
SUMMARY OF QUANTITIES

SCALE: VERT. NA
HORIZ. NA
DATE 09-18-09

DRAWN BY AG
CHECKED BY HLG