

ITEM NO.	PAY ITEM	UNIT	TOTAL QUANTITY Y047	SEGMENT A (NORTH)	SEGMENT B (MIDDLE)	SEGMENT C (SOUTH)
20101100	TREE TRUNK PROTECTION	EACH	1	0	1	0
20200100	EARTH EXCAVATION	CU YD	243	91	14	138
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	203	42	28	133
20400800	FURNISHED EXCAVATION	CU YD	80.5	20.5	0	60
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	75	0	0	75
20800150	TRENCH BACKFILL	CU YD	10	0	0	10
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	1335	245	190	900
△ 21101625	TOPSOIL, FURNISH AND PLACE, 6 INCH	SQ YD	285	25	10	250
△ 25000210	SEEDING, CLASS 2A	ACRE	0.3	0.05	0.02	0.23
△ 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	27	5	4	18
△ 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	27	5	4	18
△ 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	27	5	4	18
△ 25100115	MULCH METHOD 2	ACRE	0.3	0.05	0.02	0.23
△ 25200200	SUPPLEMENTAL WATERING	UNIT	1200	100	100	1000
28000400	PERIMETER EROSION BARRIER	FOOT	1370	250	195	925
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	52	12	0	40
31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	12	0	0	12
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	1275	222	178	875
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	325	55	44	226
40600300	AGGREGATE (PRIME COAT)	TON	2.43	0.44	0.36	1.63
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	2.13	37	30	146
42001300	PROTECTIVE COAT	SQ YD	91.5	11.5	3	77
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	650	62	0	588
42400800	DETECTABLE WARNINGS	SQ FT	124	52	24	48
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	141	48	0	93
44000600	SIDEWALK REMOVAL	SQ FT	847	0	0	847
50200100	STRUCTURE EXCAVATION	CU YD	7	0	0	7
50300225	CONCRETE STRUCTURES	CU YD	1.6	0	0	1.6
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	90	0	0	90
54202119	PIPE CULVERTS, TYPE 3 RCCP 24"	FOOT	20	0	0	20
△ 56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	1	0	0	1
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	110	0	0	110
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	24	24	0	0
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	0	0	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0	0	1
72000100	SIGN PANEL - TYPE 1	SQ FT	50	25	6.25	18.75
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	4	0	2	2
72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	2	0	2	0
72900100	METAL POST - TYPE A	FOOT	84	36	24	24
72900200	METAL POST - TYPE B	FOOT	40.5	13.5	13.5	13.5
△ 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	249	64	50	135
△ 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	412	130	77	205
78300105	PAVEMENT MARKING REMOVAL	FOOT	17	0	0	17
△ D2003860	EVERGREEN, THUJA OCCIDENTALIS TECHN (TECHNY ARBORVITAE), 5' HEIGHT, BALLED & BURLAPPED	EACH	5	5	0	0
X0322923	SEGMENTAL CONCRETE BLOCK WALL	SQ FT	97.5	97.5	0	0
XX006064	SAWCUT CURB	FOOT	30	30	0	0
Z0018400	DRAINAGE STRUCTURES TO BE ADJUSTED	EACH	1	1	0	0
Z0019600	DUST CONTROL WATERING	UNIT	18	3	3	12
67100100	MOBILIZATION	L SUM	1	1		

△: INDICATES SPECIALTY ITEMS.

REVISIONS	
NAME	DATE

URS 100 S. WACKER DR., SUITE 500 TEL (312)-939-1000
CHICAGO IL, 60606 FAX (312)-939-4198

VILLAGE OF WOODRIDGE
HERITAGE BIKEWAY
SUMMARY OF QUANTITIES

SCALE: _____ DATE: _____

DRAWN BY: Y00
CHECKED BY: DDL