

80% FED.
20% STATE

Pay Code	Item	Unit	Quantity	Mainline	Relocate Lighting	Concrete Barrier
				J000		
44002010	CONCRETE MEDIAN REMOVAL	FOOT	10.00	10.00		
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	7,976.00	7,976.00		
44002100	CONTINUOUSLY REINFORCED CONCRETE PAVEMENT REMOVAL	SQ YD	2 60,278.00	60,278.00		
44004000	PAVED DITCH REMOVAL	FOOT	4,929.00	4,929.00		
44004250	PAVED SHOULDER REMOVAL	SQ YD	2 24,858.00	24,858.00		
44200545	CLASS A PATCHES, TYPE III, 9 INCH	SQ YD	599.00	599.00		
44200547	CLASS A PATCHES, TYPE IV, 9 INCH	SQ YD	240.00	240.00		
44200559	CLASS A PATCHES, TYPE IV, 10 INCH	SQ YD	58.00	58.00		
44213000	PATCHING REINFORCEMENT	SQ YD	2 853.00	853.00		
44213200	SAW CUTS	FOOT	3,238.00	3,238.00		
48100100	AGGREGATE SHOULDERS, TYPE A	TON	2,128.00	2,128.00		
48300500	PORTLAND CEMENT CONCRETE SHOULDERS 10"	SQ YD	18.00	18.00		
48300710	PORTLAND CEMENT CONCRETE SHOULDERS 12 1/2"	SQ YD	2 28,081.00	28,081.00		
50104400	CONCRETE HEADWALL REMOVAL	EACH	14.00	14.00		
50105220	PIPE CULVERT REMOVAL	FOOT	1,323.00	1,323.00		
50300225	CONCRETE STRUCTURES	CU YD	7.80	7.80		
50800105	REINFORCEMENT BARS	POUND	23,406.00	23,406.00		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2 33,420.00	33,420.00		
5423669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	14.00	14.00		
54200049	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 18"	FOOT	104.00	104.00		
5423681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	1.00	1.00		
54215553	METAL END SECTIONS 18"	EACH	1.00	1.00		
54215979	REINFORCED CONCRETE PIPE ELBOW 24"	EACH	1.00	1.00		
5424405	FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	EACH	12.00	12.00		
54245805	INLET BOX, STANDARD 542516	EACH	5.00	5.00		
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	54.00	54.00		
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	230.00	230.00		
542A1069	PIPE CULVERTS, CLASS A, TYPE 2 24"	FOOT	1,440.00	1,440.00		
542D1069	PIPE CULVERTS, CLASS D, TYPE 2 24"	FOOT	20.00	20.00		
542A1001	PIPE CULVERTS, CLASS A, TYPE 2 36"	FOOT	88.00	88.00		
54390130	INSERTION CULVERT LINER 16"	FOOT	60.00	60.00		
54390170	INSERTION CULVERT LINER 22"	FOOT	200.00	200.00		
54390200	INSERTION CULVERT LINER 28"	FOOT	150.00	150.00		
54390220	INSERTION CULVERT LINER 32"	FOOT	80.00	80.00		
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	97.00	97.00		
60107600	PIPE UNDERDRAINS 4"	FOOT	30,989.00	30,989.00		

2 REVISD 2/23/09