

80% FED.
20% STATE

Pay Code	Item	Unit	Quantity	Mainline	Relocate Lighting	Concrete Barrier
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	2,052.00	2,052.00		J000
60218300	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	4.00	4.00		J000
60200105	CATCH BASING, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	3.00	5.00		
60264415	INLETS TO BE RECONSTRUCTED WITH NEW STANDARD 542546 FRAME AND GRATE	EACH	3.00	3.00		
60270000	DRAINAGE STRUCTURES, TYPE 4 WITH ONE TYPE 20 FRAME AND GRATE	EACH	3.00	3.00		
60270055	DRAINAGE STRUCTURES, TYPE 5 WITH TWO TYPE 22 FRAME AND GRATES	EACH	1.00	1.00		
60500060	REMOVING INLETS	EACH	13.00	13.00		
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	10,242.00	10,242.00		
60620400	CONCRETE MEDIAN, TYPE SB-9.06	SQ FT	75.00	75.00		
*63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	3,575.00	3,575.00		
*63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	6.00	6.00		
*63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	1.00	1.00		
*63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	1.00	1.00		
*63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	7.00	7.00		
63200310	GUARDRAIL REMOVAL	FOOT	2,418.00	2,418.00		
63500105	DELINEATORS	EACH	171.00	171.00		
63500310	REMOVE AND REINSTALL DELINEATORS	EACH	86.00	86.00		
63700275	CONCRETE BARRIER, DOUBLE FACE, 42 INCH HEIGHT	FOOT	1,450.00			1,450.00
63801205	TEMPORARY MODULAR GLARE SCREEN	FOOT	2,200.00	2,200.00		
64200105	SHOULDER RUMBLE STRIP	FOOT	43,193.00	43,193.00		
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2.00	2.00		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	32.00	32.00		
67100100	MOBILIZATION	L SUM	1.00	1.00		
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	6.00	6.00		
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	2.00	2.00		
70100410	TRAFFIC CONTROL AND PROTECTION, STANDARD 701416	EACH	3.00	3.00		
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1.00	1.00		
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1.00	1.00		
70100820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701451	L SUM	1.00	1.00		
70101005	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401 (SPECIAL)	EACH	4.00	4.00		
70101605	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402 (SPECIAL)	EACH	3.00	3.00		
70103710	TRAFFIC CONTROL FOR RAMPS	L SUM	1.00	1.00		

REVIS 2/23/09