

20100110 TREE REMOVAL (6 TO 15 UNITS DIAMETER)

UNIT	LOCATION	OFFSET	REMARKS
6.0	55 + 92	85.1' LT	
10.0	60 + 44	98.12' LT	
10.0	60 + 66	112.5' LT	
8.0	94 + 90	102.55' LT	
6.0	94 + 90	109.64' LT	
8.0	98 + 32	95.83' LT	
8.0	99 + 57	92.12' LT	
7.0	103 + 92	110.52' LT	
8.0	104 + 93	115' LT	
6.0	105 + 15	105' LT	
7.0	122 + 38	147' LT	
6.0	122 + 51	153.55' LT	
8.0	122 + 90	147.4' LT	
7.0	123 + 25	151.3' LT	
8.0	123 + 44	153.07' LT	
7.0	123 + 49	152.36' LT	
9.0	123 + 84	152.46' LT	
7.0	123 + 95	161.15' LT	
7.0	123 + 97	146.85' LT	
9.0	124 + 05	156.43' LT	
8.0	124 + 47	186.86' LT	
7.0	124 + 52	178.32' LT	
9.0	124 + 59	172.21' LT	
9.0	124 + 75	174.37' LT	
8.0	124 + 78	189.50' LT	
10.0	175 + 00	105' RT	
6.0	175 + 36	104.62' RT	
6.0	175 + 57	116.85' RT	
7.0	175 + 71	119.13' RT	
TOTAL		222.0	

20100210 TREE REMOVAL (OVER 15 UNITS DIAMETER)

UNIT	LOCATION	OFFSET	REMARKS
20.0	55 + 43	79.6' LT	
20.0	55 + 60	84.3' LT	
45.0	58 + 25	100' LT	
18.0	58 + 70	80.84' LT	
16.00	60 + 47	108.2' LT	
20.00	60 + 54	112.2' LT	
16.00	60 + 72	106.2' LT	
16.00	60 + 65	91.1' LT	
21.00	94 + 51	96' LT	
26.00	95 + 14	99.2' LT	
20.00	97 + 60	104.25' LT	
17.00	122 + 20	141.32' LT	
TOTAL		255.0	

20100500 TREE REMOVAL, ACRES

ACRE	LOCATION	OFFSET	REMARKS
0.07	56 + 27	58 + 22	RT
0.04	100 + 00	101 + 35	RT
0.33	103 + 25	107 + 30	RT
1.35	114 + 00	126 + 00	RT
0.22	134 + 06	136 + 00	RT
0.28	51 + 83	54 + 71	LT
1.60	72 + 00	90 + 00	LT
TOTAL		3.89	

20201006 GRADING AND SHAPING SHOULDERS

UNIT	LOCATION	REMARKS
9.28	133 + 00	141 + 07 Ramp C right shoulder
9.86	133 + 00	141 + 07 Ramp D, left shoulder
9.10	141 + 07	151 + 15 Ramp D right shoulder
10.08	141 + 07	151 + 15 Ramp D, left shoulder
9.85	110 + 00	119 + 85 Ramp C, left shoulder
11.60	108 + 26	119 + 85 Ramp C right shoulder
15.03	33 + 72	48 + 50 Ramp A pavement
4.45	48 + 50	53 + 60 Ramp A right shoulder
5.29	48 + 50	53 + 60 Ramp A, left shoulder
12.60	33 + 72	48 + 50 Ramp B pavement
3.01	78 + 70	81 + 60 Ramp B pavement
1.93	81 + 60	83 + 58 Ramp B, left shoulder
4.67	834 + 77	830 + 00 Ramp B, left shoulder
1.90	81 + 60	83 + 58 Ramp B right shoulder
4.85	834 + 77	830 + 00 Ramp B right shoulder
TOTAL		113.50

20700220 POROUS GRANULAR EMBANKMENT

CU. YD.	LOCATION	REMARKS
7.9	136 + 87	242.2' LT
TOTAL		7.90

25000750 MOWING

ACRE	LOCATION	REMARKS
20.0	51 + 52	182 + 00
TOTAL		20.00

28000300 TEMPORARY DITCH CHECKS

EACH	LOCATION	REMARKS
70.0	84 + 00	177 + 75 LT
60.0	90 + 00	177 + 75 RT
107.0	84 + 00	177 + 75 CENTER MEDIAN
6.0	84 + 00	90 + 00 RT
39.0	52 + 00	84 + 00 RT
33.0	52 + 00	84 + 00 LT
43.0	52 + 00	84 + 00 CENTER MEDIAN
TOTAL		358.00

28000400 PERIMETER EROSION BARRIER

FOOT	LOCATION	REMARKS
3223.0	84 + 00	177 + 75 LT
3107.0	84 + 00	177 + 75 RT
1336.0	52 + 00	84 + 00 RT
1829.0	52 + 00	84 + 00 LT
300.0		CONTRACTOR BORROW/WASTE SITE ENTIRE PROJECT
500.0		
TOTAL		10,295.0

28000500 INLET AND PIPE PROTECTION

EACH	LOCATION	REMARKS
21.0	84 + 00	177 + 75 LT
7.0	84 + 00	177 + 75 RT
4.0	52 + 00	84 + 00 RT
3.0	52 + 00	84 + 00 LT
TOTAL		35.0

28200200 FILTER FABRIC

SQ. YD.	LOCATION	REMARKS
455.00	53 + 67	56 + 59 LT
535.60	61 + 91	62 + 33 RT
1,457.30	63 + 17	70 + 58 RT
691.60	60 + 85	65 + 23 LT
183.30	66 + 72	66 + 82 LT
1,138.80	68 + 11	74 + 79 LT
114.40	79 + 40	80 + 11 RT
106.60	80 + 90	81 + 63 LT
274.30	82 + 00	83 + 70 LT
227.50	82 + 40	83 + 00 RT
113.10	121 + 73	122 + 48 RT
184.60	136 + 74	138 + 00 RT
1,118.00	161 + 89	169 + 54 RT
455.00	169 + 54	172 + 53 RT
260.00	172 + 54	173 + 58 RT
231.40	175 + 14	175 + 71 RT
TOTAL		7,546.5

SEE DRAINAGE SHEETS FOR ADDITIONAL QUANTITIES

28300470 AGGREGATE DITCH 12"

SQ. YD.	LOCATION	REMARKS
350.0	53 + 67	56 + 59 LT
412.0	61 + 91	62 + 33 RT
1121.0	63 + 17	70 + 58 RT
532.0	60 + 85	65 + 23 LT
141.0	66 + 72	66 + 82 LT
876.0	68 + 11	74 + 79 LT
88.0	79 + 40	80 + 11 RT
82.0	80 + 90	81 + 63 LT
211.0	82 + 00	83 + 70 LT
175.0	82 + 40	83 + 00 RT
87.0	121 + 73	122 + 48 RT
142.0	136 + 74	138 + 00 RT
860.0	161 + 89	169 + 54 RT
350.0	169 + 54	172 + 53 RT
200.0	172 + 54	173 + 58 RT
178.0	175 + 14	175 + 71 RT
TOTAL		5,805.0

31101000 SUB-BASE GRANULAR MATERIAL, TYPE B

TON	LOCATION	REMARKS
1,394.00	73 + 20	74 + 00 TEMPORARY PAVEMENT AT GORES
535.33	97 + 00	99 + 00 TEMPORARY CROSSOVER, 3" HMA,
TOTAL		1,929.33

40600200 BITUMINOUS MATERIALS (PRIME COAT)

TON	LOCATION	REMARKS
0.53	81 + 20	83 + 00 EB TAPER BETWEEN CONSTRUCTION YEARS, DOUBLE PRIME
TOTAL		0.53

40600215 POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)

TON	LOCATION	REMARKS
0.98		Ramp D pavement
0.50		Ramp D, left shoulder
0.13		Ramp D right shoulder
1.07		Ramp C pavement
0.13		Ramp C, left shoulder
0.57		Ramp C right shoulder
1.04		Ramp A pavement
0.05		Ramp A, left shoulder
0.51		Ramp A right shoulder
1.17		Ramp B pavement
0.59		Ramp B, left shoulder
0.11		Ramp B right shoulder
TOTAL		6.84

40600300 AGGREGATE (PRIME COAT)

TON	LOCATION	REMARKS
1.38	81 + 20	83 + 00 EB TAPER BETWEEN CONSTRUCTION YEARS
5.13		Ramp D pavement
2.64		Ramp D, left shoulder
0.67		Ramp D right shoulder
5.59		Ramp C pavement
0.69		Ramp C, left shoulder
2.96		Ramp C right shoulder
5.47		Ramp A pavement
0.27		Ramp A, left shoulder
2.67		Ramp A right shoulder
6.12		Ramp B pavement
3.11		Ramp B, left shoulder
0.57		Ramp B right shoulder
TOTAL		37.27

40600535 LEVELING BINDER (HAND METHOD), N70

TON	LOCATION	REMARKS
15.00	IL 84 RAMPS	RAMP LOCATIONS DETERMINED BY ENGINEER
TOTAL		15.00

2 SHEET REVISED 2/23/09