

LOCATION	REMARKS	44002100	44004250		31103000	31100910	31100935	31100965	20028415	31200500	42100350	42100950	42001300	42000551	48300710
		CONTINUOUSLY REINFORCED CONCRETE PAVEMENT REMOVAL	PAVED SHOULDER REMOVAL		SUB-BASE GRANULAR MATERIAL (SPECIAL)	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SUB-BASE GRANULAR MATERIAL, TYPE A 18"	SUB-BASE GRANULAR MATERIAL, TYPE A 24"	GEOTECHNICAL REINFORCEMENT	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4"	CONTINUOUSLY REINFORCED PCC PAVEMENT 12 1/2"	PAVEMENT REINFORCEMENT 12 1/2"	PROTECTIVE COAT	PCC PAVEMENT 12 1/2" (JOINTED)	PORTLAND CEMENT CONCRETE SHOULDERS 12 1/2"
		SQ YD	RT	LT	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD

STAGE 1E			SQ YD	RT	LT	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD
51 + 52	51 + 84	EB MAINLINE	83.17		3.97				58.22	117.54					
51 + 84	52 + 86	EB EXIT RAMP TO IL 84	333.12	35.89	14.50				233.18	171.34					69.00
51 + 84	55 + 36	EB MAINLINE								668.00					
52 + 86	55 + 36	EB EXIT RAMP TO IL 84	620.86	112.70	19.53				434.60	632.78					167.00
54 + 35	55 + 36	EB MAINLINE & BETWEEN EB EXIT RAMP TO IL 84 (GORE)	490.00	93.84	12.31				343.00	41.00					
55 + 36	58 + 00	EB MAINLINE & BETWEEN EB EXIT RAMP TO IL 84 (GORE)	1,548.31	230.59	28.72				1,083.82	388.00				388.00	
55 + 36	58 + 00	EB MAINLINE	2,177.33	955.82	178.14				1,524.13	700.00					
55 + 36	58 + 27	EB EXIT RAMP TO IL 84	47.91	24.30	11.49				33.54	806.33				516.00	205.00
58 + 00	66 + 20	EB MAINLINE								3,518.11				2,192.00	1,098.00
66 + 20	68 + 33	EB MAINLINE	585.68	255.17	101.96				409.98	1,259.33				853.00	285.00
68 + 11	69 + 42	EB ENTRANCE RAMP FROM IL 84	50.68	24.15	13.61				35.48	377.56				232.00	110.00
68 + 33	69 + 42	EB MAINLINE & BETWEEN EB ENTRANCE RAMP FROM IL 84 (GORE)	372.06		44.38				260.44	114.00				114.00	
69 + 42	70 + 40	EB MAINLINE & BETWEEN EB ENTRANCE RAMP FROM IL 84 (GORE)								31.00				31.00	
69 + 42	70 + 40	EB ENTRANCE RAMP FROM IL 84	166.49	88.36					116.54	313.89				175.00	111.00
68 + 33	86 + 00	EB MAINLINE								7,607.83				7,117.00	
70 + 40	86 + 00	EB AUXILIARY LANE								4,391.33				2,203.00	1,755.00

STAGE 1F			SQ YD	RT	LT	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD
86 + 00	89 + 58	EB MAINLINE	491.61		22.65				344.13	1,539.78					
86 + 00	86 + 68	EB AUXILIARY LANE								188.56					53.00
86 + 68	87 + 53	EB EXIT RAMP TO OVERLOOK	477.47		73.96				334.23	31.44					56.00
86 + 68	87 + 53	EB MAINLINE & BETWEEN EB EXIT RAMP TO OVERLOOK (GORE)								34.00				34.00	
87 + 53	89 + 58	EB MAINLINE & BETWEEN EB EXIT RAMP TO OVERLOOK (GORE)	881.13		89.67				616.79	343.00				343.00	
87 + 53	90 + 94	EB EXIT RAMP TO OVERLOOK	1,291.41	499.51	218.09				903.99	1,053.78				613.00	287.00
89 + 58	98 + 71	EB MAINLINE	1,149.16	492.53	217.36				804.41	5,546.89				3,673.00	1,354.00
98 + 71	101 + 81	EB MAINLINE	817.71		136.04				572.40	1,326.44				1,292.00	
98 + 02	101 + 81	EB ENTRANCE RAMP FROM OVERLOOK	264.13		43.95				184.89	1,061.11				1,240.00	283.00
98 + 71	101 + 81	EB BETWEEN MAINLINE & ENTRANCE RAMP FROM OVERLOOK (GORE)								277.00				277.00	
101 + 81	102 + 81	EB ENTRANCE RAMP FROM OVERLOOK (SHOULDER)								34.00				34.00	
101 + 81	107 + 50	EB MAINLINE	1,012.72	127.46	203.80				708.90	2,416.22				2,259.00	
102 + 81	107 + 50	EB ENTRANCE RAMP FROM OVERLOOK	159.65	43.85					111.76	1,384.11				864.00	374.00
107 + 50	111 + 42	EB ENTRANCE RAMP FROM OVERLOOK								645.56				209.00	328.00
107 + 50	111 + 42	EB MAINLINE								1,666.56				1,557.00	
111 + 42	112 + 50	EB MAINLINE								4,158.00				427.00	
112 + 50	116 + 44	EB MAINLINE	1,568.53	701.05	296.04				1,097.97	2,308.56				1,572.00	518.00
116 + 44	122 + 50	EB EXIT RAMP TO SCALE								1,304.33				696.00	434.00
116 + 44	122 + 50	EB MAINLINE								2,565.33				2,398.00	
122 + 50	132 + 50	EB MAINLINE	2,637.53	34.67	449.25				1,846.27		4,246.11			4,135.00	3,969.00
132 + 50	132 + 85	EB MAINLINE	92.22		16.06				64.55	145.89				142.00	137.00
122 + 50	131 + 56	EB EXIT RAMP TO SCALE	358.20	111.85					250.74		2,268.67			2,519.41	596.00
131 + 56	132 + 50	EB EXIT RAMP TO SCALE									231.44			221.00	62.00
132 + 50	133 + 93	EB EXIT RAMP TO SCALE								416.89				401.00	141.00
130 + 71	131 + 56	EB MAINLINE & BETWEEN EB SCALE EXIT RAMP (GORE)									30.00			30.00	
131 + 56	132 + 50	EB MAINLINE & BETWEEN EB SCALE EXIT RAMP (GORE)									107.00			107.00	
132 + 50	132 + 85	EB MAINLINE & BETWEEN EB SCALE EXIT RAMP (GORE)								66.89				63.00	107.00
132 + 85	154 + 44	EB MAINLINE	286.66	131.12	49.66				200.66	12,623.78				8,571.00	2,843.00
153 + 13	160 + 00	EB ENTRANCE RAMP FROM SCALE	557.19	193.91					390.03	1,723.33				1,076.00	457.00
160 + 00	163 + 34	EB ENTRANCE RAMP FROM SCALE	212.69	92.00					148.88		836.11			520.00	223.00
163 + 34	167 + 50	EB ENTRANCE RAMP FROM SCALE	798.92	761.17					559.24		999.22			953.00	278.00
167 + 50	171 + 85	EB ENTRANCE RAMP FROM SCALE								740.33				692.00	361.00
154 + 44	160 + 00	EB MAINLINE & BETWEEN EB ENTRANCE RAMP FROM SCALE (GORE)								1,005.00				1,005.00	
160 + 00	163 + 34	EB MAINLINE & BETWEEN EB ENTRANCE RAMP FROM SCALE (GORE)									273.00			273.00	
163 + 34	164 + 34	EB MAINLINE & BETWEEN EB ENTRANCE RAMP FROM SCALE (GORE)									34.00			34.00	
154 + 44	160 + 00	EB MAINLINE	1,240.93		213.21				868.65	2,381.78				2,227.00	
160 + 00	167 + 50	EB MAINLINE	1,989.23		347.68				1,392.46		3,208.33			3,000.00	
167 + 50	171 + 85	EB MAINLINE	1,149.67		201.45				804.77	1,860.33				1,740.00	
171 + 84	177 + 75	EB MAINLINE	1,566.86	661.65	272.92				1,096.80	3,474.33				2,361.00	786.00
177 + 75	180 + 00	INSIDE EB MAINLINE SHOULDER								242.00					217.00
177 + 75	180 + 00	OUTSIDE EB MAINLINE SHOULDER		254.35	126.30					297.00					272.00

REVISION: 2 REVISED SHEET 2/23/09	TOTALS	60,277.15	24,858.05	42,194.01	139,472.37	11,811.22	25,516.44	174,618.43	163,473.70	117,810.20	117,810.20	59,185.00	10,377.00	28,081.00
-----------------------------------	--------	-----------	-----------	-----------	------------	-----------	-----------	------------	------------	------------	------------	-----------	-----------	-----------

FILE NAME =	USER NAME = grantpm	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>PAVEMENT SCHEDULE</b>	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
ct:\pwork\pvidot\grantpm\dms34287\d08403covr.dgn		DRAWN -	REVISED -			80	(81-1) R-1	ROCK ISLAND	292	42		
PLOT SCALE = 100,000' / IN.		CHECKED -	REVISED -			CONTRACT NO. 64933						
PLOT DATE = Wed Feb 11 15:46:30 2009		DATE -	REVISED -			SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.