

PIPE CULVERTS, CLASS A, TYPE 1 24" (542A0229)									
PIPE NUMBER	STATION	OFFSET	INVERT	STATION	OFFSET	INVERT	FOOT	TRENCH BACKFILL (CUYD)	
47	60+37	0'	618.10	60+37	56' RT	617.83	54.0	5	
							TOTAL	54.0	5

PIPE CULVERTS, CLASS A, TYPE 2 24" (542A1069)									
PIPE No.	STATION	OFFSET	INVERT	STATION	OFFSET	INVERT	FOOT	TRENCH BACKFILL (CUYD)	
2	67+00	3.87 LT	637.86	67+00	85.56 LT	637.09	76	17	
4	81+00	0.0 LT	674.74	81+00	108.38' LT	672.84	32	18	
6	111+00	5.1' LT	686.50	111+00	105.6' LT	686.00	103	30	
8	124+97	3.92 LT	676.63	124+97	98.77' RT	676.14	101	65	
9	135+98	3.88 LT	682.61	135+98	89.96 LT	681.92	83	24	
18	135+98	89.96 LT	681.92	136+54	215.63 LT	668.55	135	58	
30	53+05	0.9 LT	602.17	53+05	58.6 LT	601.86	59	17	
31	63+88	121.3' LT	624.29	64+22	67' LT	627.22	64	25	
37	132+00	3.82 LT	678.91	132+00	113.8' RT	678.33	114	64	
46	155+00	1.2' LT	682.96	155+00	93.6' LT	682.03	93	52	
48	62+00	0'	621.61	62+01	68.4' RT	621.25	70	37	
49	64+50	5.6' LT	627.56	64+22	67' LT	627.22	62.0	44	
50	143+75	85.6' RT	688.21	143+75	1.8' LT	687.77	88.0	65	
51	143+75	5.8' LT	687.57	143+75	76' LT	687.21	71.0	94	
52	143+75	80.8' LT	686.76	143+75	124.4' LT	686.54	44.0	40	
24	128+00	0'	677.45	128+00	80.77' LT	677.07	75.0	64	
26	128+00	84.77' LT	677.05	128+00	210.8' LT	676.42	127.0	52	
28	154+00	72.9' RT	685.21	154+00	119.3' RT	684.75	47.0	24	
							TOTAL	1444.0	790

CULVERT TO BE CLEANED (Z0014800)		
STATION	SIZE	LENGTH
	(INCHES)	(FEET)
59+95	36	260
79+81	36	271
82+50	18	331
104+00	36	450
122+49	60	500
124+82 LT	24	145
128+99 LT	24	155
13452 RT	24	157
13506 RT	24	137
135+85 RT	24	145
136+81	36	625
137+99 RT	24	62
147+63	36	540
173+55	36	540
173+97 LT	24	110
183+00	18	355
161+97 LT	24	108
161+97 LT	36	76
IL 84 RAMPS		
62+30 RT	24	75
63+01 RT	24	86
66+27 LT	36	83
66+81 LT	12	24
67+19 LT	36	100
TOTAL		5335

REINFORCED CONCRETE PIPE ELBOW 24" (54215979)				
PIPE No.	STATION	OFFSET	ANGLE	EACH
4A	81+00	74.5' LT	7.50	1
			TOTAL	1.0

INSERTION CULVERT LINER 16" (54390130)								
PIPE No.	STATION	OFFSET	INVERT	STATION	OFFSET	INVERT	FOOT	
44	104+89	123.1' LT	687.20	104+89	184.2' LT	682.70	60	
							TOTAL	60

PIPE CULVERTS, CLASS D, TYPE 1 18" (542D0223)									
PIPE No.	STATION	OFFSET	INVERT	STATION	OFFSET	INVERT	FOOT	TRENCH BACKFILL (CUYD)	
35	86+10	2.6' RT	691.72	83+72	0.5' LT	688.50	230	0	
							TOTAL	230.0	0

INSERTION CULVERT LINER 28" (54390200)								
PIPE No.	STATION	OFFSET	INVERT	STATION	OFFSET	INVERT	FOOT	
25	136+87	242.2' LT	665.89	137+96	340' LT	643.78	147	
							TOTAL	147.0

PIPE CULVERTS, CLASS D, TYPE 2, 24" (542D1069)									
PIPE No.	STATION	OFFSET	INVERT	STATION	OFFSET	INVERT	FOOT	TRENCH BACKFILL (CUYD)	
27	173+97	200' LT	Match Existing	173+97	220' LT	626.51	20	0	
							TOTAL	20.0	0

2 REVISED SHEET 2/23/09