

28100101	STONE RIPRAP, CLASS A1			
	SQ YD	LOCATION	OFFSET	REMARKS
	13.0	63 + 88	121.3' LT	
	24.0	80 + 49	154' LT	
	154.0	80 + 73	98-174' LT	
	44.0	80 + 60	182' LT	
	77.0	81 + 36	98' LT	
	13.0	81 + 02	93.4' LT	
	350.0	83 + 00	119' LT	
	827.0	167 + 00	92' RT	
	575.0	171 + 50	92-147' RT	
TOTAL	2077.0			

28100109	STONE RIPRAP, CLASS A5			
	SQ YD	LOCATION	OFFSET	REMARKS
	24.0	80 + 49	154' LT	
	154.0	80 + 73	98-174' LT	
	575.0	171 + 50	92-147' RT	
TOTAL	753.0			

28400100	GABIONS			
	CU YD	LOCATION	OFFSET	REMARKS
	10.5	136 + 87	242' LT	
TOTAL	10.5			

28100105	STONE RIPRAP, CLASS A3			
	SQ YD	LOCATION	OFFSET	REMARKS
	11.0	53 + 05	58.6' LT	
	40.0	59 + 00	125' RT	
	11.0	60 + 37	56' RT	
	11.0	62 + 01	68.4' RT	
	11.0	67 + 01	86.7' LT	
	12.0	82 + 76	53' LT	
	8.0	86 + 26	0' RT	
	20.0	102 + 77	204' LT	
	12.0	104 + 92	189' LT	
	12.0	104 + 92	119' LT	
	11.0	111 + 00	105.6' LT	
	100.0	121 + 19	180' RT	
	20.0	121 + 73	108' RT	
	175.0	123 + 00	147' RT	
	33.0	123 + 65	272' LT	
	11.0	124 + 33	278' LT	
	11.0	128 + 11	188' LT	
	11.0	132 + 00	112.1' RT	
	170.0	133 + 37	148' RT	
	9.0	135 + 28	209.2' RT	
	100.0	136 + 87	249' RT	
	30.0	138 + 18	352' LT	
	20.0	148 + 55	247' RT	
	11.0	155 + 00	93.6' LT	
	15.0	161 + 97	192' LT	
	220.0	163 + 00	101' RT	
	40.0	171 + 94	222' RT	
	15.0	173 + 99	220' LT	
	100.0	174 + 56	120' LT	
	100.0	178 + 96	163' LT	
	15.0	178 + 96	260' LT	
TOTAL	1365.0			

28200200	FILTER FABRIC			
	SQ YD	LOCATION	OFFSET	REMARKS
	11.0	53 + 05	58.6' LT	
	40.0	59 + 00	125' RT	
	11.0	60 + 37	56' RT	
	11.0	62 + 01	68.4' RT	
	13.0	63 + 88	121.3' LT	
	11.0	67 + 01	86.7' LT	
	24.0	80 + 49	154' LT	
	154.0	80 + 73	98-174' LT	
	44.0	80 + 60	182' LT	
	77.0	81 + 36	98' LT	
	13.0	81 + 02	93.4' LT	
	12.0	82 + 76	53' LT	
	350.0	83 + 00	119' LT	
	8.0	86 + 26	0' RT	
	20.0	102 + 77	204' LT	
	12.0	104 + 92	189' LT	
	12.0	104 + 92	119' LT	
	11.0	111 + 00	105.6' LT	
	100.0	121 + 19	180' RT	
	20.0	121 + 73	108' RT	
	175.0	123 + 00	147' RT	
	33.0	123 + 65	272' LT	
	11.0	124 + 33	278' LT	
	11.0	128 + 11	188' LT	
	11.0	132 + 00	112.1' RT	
	170.0	133 + 37	148' RT	
	9.0	135 + 28	209.2' RT	
	100.0	136 + 87	249' RT	
	30.0	138 + 18	352' LT	
	20.0	148 + 55	247' RT	
	11.0	155 + 00	93.6' LT	
	15.0	161 + 97	192' LT	
	220.0	163 + 00	101' RT	
	40.0	171 + 94	222' RT	
	15.0	173 + 99	220' LT	
	100.0	174 + 56	120' LT	
	100.0	178 + 96	163' LT	
	15.0	178 + 96	260' LT	
TOTAL	3442.0			

28100107	STONE RIPRAP, CLASS A4			
	SQ YD	LOCATION	OFFSET	REMARKS
	13.0	63 + 88	121.3' LT	
	44.0	80 + 60	182' LT	
	77.0	81 + 36	98' LT	
	13.0	81 + 02	93.4' LT	
	350.0	83 + 00	119' LT	
	827.0	167 + 00	92' RT	
TOTAL	1324.0			

REVISOR: [Signature] DATE: 2/23/09

FILE NAME =	USER NAME = grantpm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	DRAINAGE SCHEDULE				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pwwork\pwwork\grantpm\dms34287\d08403.dgn	DRAWN -	REVISED -	80						(81-1) R-1	ROCK ISLAND	292	46	
PLOT SCALE = 100.000' / IN.	CHECKED -	REVISED -	SCALE: SHEET NO. OF SHEETS STA. TO STA.				CONTRACT NO. 64933						
PLOT DATE = Wed Feb 11 15:46:31 2009	DATE -	REVISED -	FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT										