

80% FED
20% STATE

Pay Code	Item	Unit	Quantity	Mainline J000	Relocate Lighting J000	Concrete Barrier J000
* Z0030030	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2.00	2.00		
* Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2.00	2.00		
* Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	2.00	2.00		
Z0056220	SAND MODULE IMPACT ATTENUATOR TO BE REMOVED	EACH	24.00	24.00		
Z0076870	UNDERDRAIN CONNECTION TO STRUCTURE	EACH	12.00	12.00		
* A2001714	TREE, ACER SACCHARUM (SUGAR MAPLE), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	50.00	50.00		
* A2005014	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	25.00	25.00		
* A2006514	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	50.00	50.00		
* A2006714	TREE, QUERCUS MACROCARPA (BUR OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	50.00	50.00		
* B2004514	TREE, MALUS RED JEWEL (RED JEWEL CRAB APPLE), 1-3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	44.00	44.00		
* B2004814	TREE, MALUS SARGENTII (SARGENT CRABAPPLE) 1-3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	40.00	40.00		
XX001874	PERMANENT DITCH CHECKS	EACH	4.00	4.00		
XX002866	CONCRETE BARRIER WALL (SPECIAL)	CU YD	69.00	69.00		
XX003503	FLARED END SECTION REMOVAL	EACH	4.00	4.00		
* XX003982	VIDEO VEHICLE DETECTION SYSTEM	L SUM	1.00	1.00		
XX004033	CLEAN EXISTING CULVERTS	EACH	23.00	23.00		
* X0321478	MAINTENANCE OF EXISTING LIGHTING SYSTEM COMPLETE	L SUM	1.00		1.00	
* X0322352	SEEDING MOBILIZATION	EACH	4.00	4.00		
* X0324652	TRACER CABLE	FOOT	11,202.00	8,321.00	2,881.00	
* X0324915	RELOCATE LIGHTING UNITS AND POLES	EACH	15.00		15.00	
X0349800	CONCRETE HEADWALL FOR PIPE UNDERDRAIN REMOVAL	EACH	8.00	8.00		
* X0325194	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3, SPECIAL	EACH	1.00			1.00
X0712400	TEMPORARY PAVEMENT	SQ YD	634.00	634.00		
X0919000	TEMPORARY PAVEMENT REMOVAL	SQ YD	634.00	634.00		
X4400198	CONCRETE BARRIER REMOVAL (SPECIAL)	FOOT	460.00			460.00
X6050700	REMOVE INLET BOX	EACH	6.00	6.00		
* X7050167	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)	EACH	5.00	5.00		
* X7330105	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	133.95	133.95		
X8410105	TEMPORARY LIGHTING SYSTEM	EACH	2.00	2.00		
* X0326207	REMOVE AND REPLACE WEATHER STATION	L SUM	1.00	1.00		
* X0326274	REAL-TIME TRAFFIC CONTROL SYSTEM	L SUM	1.00	1.00		

* SPECIALITY ITEMS

FILE NAME =	USER NAME = grantpm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\psdot\grantpm\dms34287\d084	03crr.dgn	DRAWN -	REVISED -						80	(81-1) R-1	ROCK ISLAND	292	9
	PLOT SCALE = 100.000' / IN.	CHECKED -	REVISED -		SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	CONTRACT NO. 64933			
	PLOT DATE = Mon Dec 15 09:42:11 2008	DATE -	REVISED -		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT								