

# GENERAL NOTES

ROUTE NO.	SEC.	COUNTY	TOTAL SHEETS	SHEET NO.
FAI 80 (I-80)	(81-1)R-1	Rock Island	292	12
FED ROAD DIST. NO.	ILLINOIS	PROJECT		
Contract #64933				

Tie bars shall be installed to tie PCC appurtenance to adjacent existing concrete pavement.

Tie the following  
to the existing  
concrete pavement

Length, size, and  
spacing of Tie Bars

Gutter or Curb & Gutter	Std. 606001	600 mm (24") long No. 20 (No. 6) @ 600 mm (24") centers
PCC Base Course	Std. 353001	600 mm (24") long No. 20 (No. 6) @ 750 mm (30") centers
PCC Pavement	Std. 420101	600 mm (24") long No. 20 (No. 6) @ 750 mm (30") centers

Tie bars to be installed in accordance with the applicable portions of Article 420.05(b) of the Standard Specifications. See Highway Standard 420001 for detail on longitudinal construction joint grouted-in-place tie bar. The cost of the tie bars to be included in the cost of the PCC appurtenance adjacent to the existing pavement.

CADD data will be available to Contractors and Consultants working on this project. This information will be provided upon request as MicroStation CADD files and Geopak coordinate geometry files ONLY. If data is required in other formats it will be your responsibility to make these conversions. If any discrepancy or inconsistency arises between the electronic data and the information on the hard copy, the information on the hard copy should be used. Contact the District's Project Engineer to request these files.

The Contractor shall not use the scenic overlook for any project activities.

The Contractor shall not use the IL 84 infields for any project activities without prior written approval by the District Landscape Architect.

The Contractor shall remove the existing median crossover wood posts, cable, sign supports, and panels. This work shall be included in the various removal pay items and no additional compensation will be allowed.

The Contractor shall replace both median crossover closure components (posts, cable, panels) to that shown in the District Two Standard 98.4, TYPICAL MEDIAN CROSSOVER CLOSURE. This work shall be included in the various traffic control pay items and no additional compensation will be allowed.

Program #5  
(Arch. Size)  
Enlarge  
200%  
Enlarge 107%