



- 15 REINFORCED CONCRETE END SECTIONS 24" STA. 155+00/93.6' LT CONCRETE STRUCTURES 1.0 CU YD (50300225) REINFORCEMENT BARS, EPOXY COATED 35 LBS (50800205) INV.- 682.06
- 16 REINFORCED CONCRETE END SECTIONS 36" STA. 161+98/189' LT CONCRETE STRUCTURES 1.0 CU YD (50300225) REINFORCEMENT BARS, EPOXY COATED 35 LBS (50800205) INV.- 657.29
- 12 FLUSH INLET BOX FOR MEDIAN, STANDARD 542546 (54244405) STA. 155+00/1.2' LT RIM- 687.44 INV- 682.51
- 13 FLUSH INLET BOX FOR MEDIAN, STANDARD 542546 (54244405) STA. 161+97/0' RIM- 675.64 INV- 670.64

- 14 CB, TA, 4'-DIA. TIF, OL (60200105) STA. 161+97/112.3' LT RIM- 670.30 INV.- 664.56
- 15 STONE RIPRAP CL A3 (28100105) 11 S.Y. (6'W X 16'L) FILTER FABRIC (28200200) 11 S.Y. (6'W X 16'L)

- 22 PIPE CULVERTS, CL. A, TY. 2 24" (542A1069) 108' @ 5.62% TBF= 61 CY
- 26 INSERTION CULVERT LINER 32" (54390220) 77'
- 46 PIPE CULVERTS, CL. A, TY. 2 24" (542A1069) 90' @ 0.50% TBF= 52 CY

FILE NAME: c:\new\_work\pudct\grant\pudct\jms\34287\_d88483dr.dgn

MATCH LINE STA 164+00  
SEE SHEET NO.