Summary of Quantities

	Pay Item #	Description	Unit	Total Quantity	80 % Fed 20% State I000	80 % Fed 20% State X028-2A	80 % Fed 20% State Y007
	20100110	Tree Removal (6 to 15 units diameter)	Unit	126.0	126.0		
	20100210	Tree Removal (Over 15units diameter)	Unit	124.0	124.0		
	20100500	Tree Removal, Acres	Acre	0.25	0.25		
	20200100	Earth Excavation	Cu Yd	4212.0	4212.0		
	20201200	Removal and Disposal of Unsuitable Material	Cu Yd	100.0	100.0		
*	25000210	Seeding, Class 2A	Acre	1.25	1.25		
*	25000310	Seeding, Class 4	Acre	0.75	0.75		
*	25000400	Nitrogen Fertilizer Nutrient	Pound	180.0	180.0		
*	25000500	Phosphorus Fertilizer Nutrient	Pound	180.0	180.0		
*	25000600	Potassium Fertilizer Nutrient	Pound	180.0	180.0		
:)	25000750	Mowing	Acre	2.0	2.0		
	25100115	Mulch, Method 2	Acre	2.0	2.0		
	25100630	Erosion Control Blanket	Sq Yd	1204.0	1204.0		
	28000250	Temporary Erosion Control Seeding	Pound	1200.0	1200.0		
	28000300	Temporary Ditch Checks	Each	60.0	60.0		
	28000400	Perimeter Erosion Barrier	Foot	100.0	100.0		
	28000500	Inlet and Pipe Protection	Each	2.0		1	1
	35101600	Aggregate Base Course, Type B 4"	Sq Yd	744.0	744.0		
	40603310	Hot-Mix Asphalt, Surface Course , Mix "C", N50	Ton	83.3	83.3		
	44201383	Class C Patches, Type IV, 12 Inch	Sq Yd	549.0	188.0	233	128
	44300200	Strip Reflective Crack Control Treatment	Foot	370.0	370.0		
	48101500	Aggregate Shoulders, Type B 6"	Sq Yd	34.0	34.0		
	48203021	Hot-Mix Asphalt Shoulders, 6"	Sq Yd	743.5	743.5		
	50100300	Removal of Existing Structures No. 1	Each	1.0		1	
	50100400	Removal of Existing Structures No. 2	Each	1.0			1
*	50104400	Concrete Headwall Removal	Each	1.0	1.0		
	50800105	Reinforcement Bars	Pound	19200.0		19200	
	50800205	Reinforcement Bars, Epoxy Coated	Pound	740.0		740	
	51205200	Temporary Sheet Piling	Sq Ft	2,519.0		1,513	1,006
	51500100	SPACE Nameplates	Each	2.0		1	1
	54001001	Box Culvert End Section,Culvert No. 1	Each	1.0			1
	54010804	Precast Concrete Box Culvert 8'x4'	FOOT	90.0			90
	54010808	Precast Concrete Box Culvert 8'x8'	FOOT	198.0		198	
	54003000	Concrete Box Culverts	Cu Yd	156.4		156.4	
	61133100	Field Tile Junction Vaults, 2' Dia.	Each	2.0	2.0		
	61140000	Storm Sewers, Special 8"	Foot	160.0	100.0		
	61140100	Storm Sewers, Special 10"	Foot	100.0	100.0		

				Total	80 % Fed 20% State I000	80 % Fed 20% State X028-2A	80 % Fed 20% State Y007
	61140200	Storm Sewers, Special 12"	Foot	100.0	100.0		
*	63000000	Steel Plate Beam Guardrail, Type A	Foot	612.5	612.5		
	63100167	Traffic Barrier Terminal, Type 1 (Special) Tangent	Each	4.0	4.0		
	63200310	Guardrail Removal	Foot	898.0	898.0		
	63500105	Delineators	Each	11.0	4	2	5
	66600105	Furnishing and Erecting Right-of-Way Markers	Each	27.0	27.0		
	66700305	Permanent Survey Markers, Type II	Each	4.0	4.0		
	67000400	Engineer's Field Office, Type A	Cal Mo	6.0	6.0		
	67100100	Mobilization	L Sum	1.0	1.0		
	70100405	Traffic Control and Protection, Standard 701321	Each	1.0	1.0		
	70100450	Traffic Control and Protection, Standard 701201	L Sum	1.0	1.0		
	70100460	Traffic Control and Protection, Standard 701306	L Sum	1.0	1.0		
	70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1.0	1.0		
	70103815	Traffic Control Surveillance	Cal Da	10.0	10.0		
	70106500	Temporary Bridge Traffic Signals	Each	3.0		1	2
	70106700	Temporary Rumble Strip	Each	12.0		6	6
	70300220	Temporary Pavement Marking - Line 4"	Foot	5,289.0		2,223	3,066
	70300280	Temporary Pavement Marking - Line 24"	Foot	55.0		27	28
	70301000	Workzone Pavement Marking Removal	Sq Ft	1,873.0		795	1,078
	70400100	Temporary Concrete Barrier	Foot	1,075.0		437.5	637.5
	70400200	Relocate Temporary Concrete Barrier	Foot	1,000.0		387.5	612.5
*	78001110	Paint Pavement Marking - Line 4"	Foot	7,012.0		2,908	4,104
*	78200410	Guardrail Markers, Type A	Each	16.0	16.0		
*	78201000	Terminal Marker - Direct Applied	Each	4.0	4.0		
	78300100	Pavement Marking Removal	Sq Ft	1,594.0		811	783
*	A2006714	TREE, Quercus Macrocarpa (Bur Oak), 1-3/4" Caliper, Balled and Burlapped	Each	14.0	14.0		
*	C2001548	SHRUB, Cornus Racemosa (Grey Dogwood), 4' Height, Balled and Burlapped	Each	20.0	20.0		
	X0323660	Drop Box No.1	Each	1.0			1
	X0712400	Temporary Pavement	Sq Yd	770.0			770
	Z0013798	Construction Layout	L Sum	1.0	1.0		
	Z0023600	Filling Existing Culverts	Each	1.0	1.0		
	Z0030250	Impact Attenuators, Temporary (Non-RE Directive), Test Level 3	Each	4.0	4.0		
	Z0030350	Impact Attenuators, Relocate (Non-RE Directive), Test Level 3	Each	4.0	4.0		

* SPECIALTY ITEM
:) NON-PARTICIPATING
100% STATE

REVISED 2-24-09

FILE NAME = c:\pw_work\pwidot\fordjd\dms33877\D264A07-sht-S00.dgn	USER NAME = fordjd	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 50.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = Tue Dec 30 07:37:37 2008	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL251

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1177	111T	LASALLE	59	2

CONTRACT NO. 64A07

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT