

Schedule of Quantities

Pay Item #	Description	Unit	Comments
2519 + 50 - 2520 + 40	LT	60.77	
2520 + 81 - 2523 + 00	LT	147.90	
2519 + 50 - 2520 + 75	RT	84.07	
2521 + 25 - 2523 + 00	RT	118.59	
Total =		1204.25	
28000250	Temporary Erosion Control Seeding	Pound	
<u>Location</u>			
2472 + 50 - 2478 + 50	RT	275.00	
2471 + 00 - 2478 + 00	LT	275.00	
2518 + 00 - 2523 + 50	RT	325.00	
2518 + 00 - 2523 + 50	LT	325.00	
Total =		1200.00	
28000300	Temporary Ditch Checks	Each	
<u>Location</u>			
2471 + 00 - 2471 + 50	LT	1	20' Centers
2471 + 50 - 2472 + 50	LT	3	33' Centers
2472 + 50 - 2477 + 00	LT	9	50' Centers
2518 + 00 - 2519 + 50	LT	5	33' Centers
2519 + 50 - 2520 + 00	LT	2	25' Centers
2520 + 00 - 2520 + 38.75	LT	1	40' Centers
2520 + 81.6 - 2523 + 00	LT	10	25' Centers
2473 + 00 - 2477 + 50	RT	10	50' Centers
2518 + 00 - 2520 + 75	RT	10	25' Centers
2521 + 30 - 2522 + 50	RT	7	20' Centers
2522 + 50 - 2523 + 00	RT	2	25' Centers
Total =		60	
28000400	Perimeter Erosion Barrier	Foot	
<u>Location</u>			
2476 + 00 - 2477 + 00	37' LT	100	
Total =		100	
28000500	Inlet and Pipe Protection	Each	
<u>Location</u>			
2472 + 75	56.67' LT	1	
2520 + 90.3	37.7' RT	1	
Total =		2	
35101600	Aggregate Base Course, Type B 4"	Sq. Yd.	
<u>Location</u>			
2518 + 32.3 - 2522 + 88.9	RT	375.1	
2518 + 75.0 - 2523 + 19.0	LT	368.4	
Total =		744.0	
40603310	Hot Mix Asphalt, Surface Course, Mix "C" N50	Ton	
<u>Location</u>			
2518 + 32.3 - 2522 + 88.9	RT 2"	42.06	
2518 + 75.0 - 2523 + 19.0	LT 2"	41.25	
Total =		83.3	
44201383	Class C Patches, Type IV, 12 inch	Sq. Yd.	
<u>Location</u>			
2472 + 54.3 - 2472 + 95.7		128	
2475 + 13.0 - 2475 + 73.5		188	
2520 + 42.1 - 2521 + 19.8		233	
Total =		549	

Pay Item #	Description	Unit	Comments
44300200	Strip Reflective Crack Control Treatment	Foot	
<u>Location</u>			
2519 + 15.1 - 2522 + 85.4	20.4' RT	370	
Total =		370	
48101500	Aggregate Shoulders, Type B 6"	Sq. Yd.	
<u>Location</u>			
2472 + 44.5 - 2473 + 05.5	RT	13.8	
2475 + 20.5 - 2475 + 66.5		20.3	
Total =		34.1	
48203019	Hot-Mix Asphalt Shoulders, 6"	Sq. Yd.	
<u>Location</u>			
2518 + 32.3 - 2522 + 88.9	RT	375.07	
2518 + 75.0 - 2523 + 19.0	LT	368.38	
Total =		743.45	
50100300	Removal of Existing Structures No. 1	Each	
<u>Location</u>			
2520 + 80.74		1	
Total =		1	
50100400	Removal of Existing Structures No. 2	Each	
<u>Location</u>			
2475 + 43.7		1	
Total =		1	
50104400	Concrete Headwall Removal	Each	
<u>Location</u>			
2743 + 0.8		1	
Total =		1	
50800105	Reinforcement Bars	Pound	
<u>Location</u>			
2520 + 72.0	LT	9600	
2520 + 90.0	RT	9600	
Total =		19200	
50800205	Reinforcement Bars, Epoxy Coated	Pound	
<u>Location</u>			
2520 + 72.0	LT	370	
2520 + 90.0	RT	370	
Total =		740	
51205200	Temporary Sheet Piling	Sq. Ft.	
<u>Location</u>			
2520 + 40.08 - 2520 + 66.55	0.65' RT	1513.1	
2472 + 52.3 - 2472 + 97.7		1006	
Total =		2519.1	
51500100	Nameplate	Each	
<u>Location</u>			
2472 + 75 (See District Standard 89.4)		1	
2520 + 81 (See State Standard 515001-03)		1	
Total =		2	
54001001	Box Culvert End Section, Culvert No. 01	Each	
<u>Location</u>			
2472 + 75	RT	1	
Total =		1	

REVISIED SHEET 2-24-09