

Schedule of Quantities

Pay Item #	Description	Unit	Comments	Pay Item #	Description	Unit	Comments
54010804	Precast Concrete Box Culvert 8'x4'	Foot		63500105	Delineators	Each	
	Location				Location		
	2472 + 75	90			2472 + 70.3 57.2' LT	1	
	Total =	90			2472 + 70.3 61.8' LT	1	
54010808	Precast Concrete Box Culvert 8'x8'	Foot			2472 + 70.3 45' LT	1	
	Location				2472 + 79.7 57.2' LT	1	
	2520 + 81 (THREE)	198			2472 + 79.7 61.8' LT	1	
	Total =	198			2519 + 09.26 RT	1	
54003000	Concrete Box Culverts	Cu. Yd.			2519 + 51.91 LT	1	
	Location				2520 + 74.7 34.8' RT	1	
	2520 + 72.0 LT	78.2			2520 + 87.3 34.8' LT	1	
	2520 + 90.0 RT	78.2			2522 + 10.09 RT	1	
	Total =	156.4			2522 + 52.75 LT	1	
61133100	Field Tile Junction Vaults, 2' Dia.	Each		66600105	Furnishing and Erecting Right-of-Way Markers	Each	
	Location				Location		
	2472 + 84.5 74.2' RT	1			2470 + 00 40' LT	1	
	2475 + 16.41 28.2' LT	1			2471 + 00 40' RT	1	
	Total =	2			2472 + 00 50' RT	1	
61140000	Storm Sewer, Special 8"	Foot			2472 + 00 55' LT	1	
	Location				2472 + 50 95' RT	1	
	2472 + 84.5 74.2' RT	50	If Necessary		2472 + 50 85' LT	1	
	2475 + 16.41 28.2' LT	50	If Necessary		2473 + 00 95' RT	1	
	Total =	100			2473 + 00 85' LT	1	
61140100	Storm Sewer, Special 10"	Foot			2474 + 00 65' RT	1	
	Location				2474 + 00 60' LT	1	
	2472 + 84.5 74.2' RT	50	If Necessary		2476 + 00 60' RT	1	
	2475 + 16.41 28.2' LT	50	If Necessary		2477 + 82.89 55' RT	1	
	Total =	100			2478 + 00 40' RT	1	
61140200	Storm Sewer, Special 12"	Foot			2517 + 00 40' RT	1	
	Location				2517 + 00 40' LT	1	
	2472 + 84.5 74.2' RT	50	If Necessary		2518 + 00 50' RT	1	
	2475 + 16.41 28.2' LT	50	If Necessary		2518 + 00 50' LT	1	
	Total =	100			2520 + 00 90' LT	1	
63000000	Steel Plate Beam Guardrail, Type A	Foot			2520 + 25 120' LT	1	
	Location				2520 + 50 100' RT	1	
	2519 + 09.26 - 2522 + 10.09 RT	300.84			2520 + 75 120' LT	1	
	2519 + 51.91 - 2522 + 52.75 LT	300.84			2521 + 00 90' LT	1	
	Total =	612.5			2521 + 00 100' RT	1	
63100167	Traffic Barrier Terminal, Type 1 (Special), Tangent	Each		66700305	Permanent Survey Markers, Type II	Each	
	Location				Location		
	2519 + 09.26 RT	1			To be determined by contractor @ both working areas	4	
	2522 + 10.09 RT	1			Total =	4	
	2519 + 51.91 LT	1					
	2522 + 52.75 LT	1					
	Total =	4					
63200310	Guardrail Removal	Foot		70106500	Temporary Bridge Traffic Signals	Each	
	Location				Location		
	2474 + 67.9 - 2475 + 95.9 RT	128.35			2517 + 73.3 RT	1	
	2474 + 91.3 - 2476 + 19.2 LT	128.2			2517 + 98.3 LT	1	
	2519 + 29.76 - 2522 + 31.69 RT	319.75			2524 + 14.1 RT	1	
	2519 + 29.69 - 2522 + 31.61 LT	322.06			2524 + 39.1 LT	1	
	Total =	898.36			Nth 45th Rd	2	
					Total =	6	

2 REVISIED SHEET 2-24-09