

Schedule of Quantities

Pay Item #	Description	Unit	Comments	Pay Item #	Description	Unit	Comments
70106700	Temporary Rumble Strips To be placed according to Traffic Control and Protection, Standards 701316-03, 701321-09	Each		78200410	Guardrail Markers, Type A	Each	
		12			Location As per State Standard 635006-02	16	
		Total=				Total=	
		12				16	
70300220	Temporary Pavement Marking - Line 4"	Foot		78201000	Terminal Marker - Direct Applied	Each	
	Location				Location		
	2468 + 53.2 - 2477 + 80.8 (Stage 1)	930.4			2519 + 09.26 RT	1	
	2470 + 71.3 - 2477 + 26.5 (Stage 1)	654.8			2522 + 10.09 RT	1	
	2469 + 54.6 - 2478 + 53.7 (Stage 2)	901.4			2519 + 51.91 LT	1	
	2470 + 97.4 - 2476 + 72.5 (Stage 2)	579.6			2522 + 52.75 LT	1	
	2516 + 93.1 - 2524 + 17.4 (Stage 1)	727.0				Total=	4
	2518 + 78.3 - 2522 + 93.4 (Stage 1)	426.0					
	2517 + 87.9 - 2524 + 45.8 (Stage 2)	660.0		78300100	Pavement Marking Removal	Sq. Ft.	
	2519 + 05.9 - 2522 + 45.0 (Stage 2)	410.0			Location		
	Total=	5289			2469 + 54.6 - 2478 + 53.7 LT	299.7	
					2469 + 54.6 - 2478 + 53.7 Centerline	299.7	
70300280	Temporary Pavement Marking - Line 24"	Foot			2468 + 53.2 - 2477 + 80.8 RT	309.2	
	Location				2516 + 83.1 - 2524 + 45.8 Centerline	254.2	
	2468 + 43.2	14.8			2516 + 83.1 - 2523 + 46.5 RT	221.1	
	2478 + 63.7	13.75			2518 + 14.9 - 2524 + 45.8 LT	210.3	
	2516 + 83.1	13			Total=	1594.3	
	2524 + 77.4	13.6					
	Total=	55.15		X0323660	Drop Box No.1	Each	
					Location		
70301000	Workzone Pavement Marking Removal	Sq. Ft.			2472 + 75.0	1	
	Location				Total=	1	
	2468 + 53.2 - 2477 + 80.8 (Stage 1)	310.1		X0712400	Temporary Pavement	Sq. Yd.	
	2470 + 71.3 - 2477 + 26.5 (Stage 1)	218.2			Location		
	2469 + 54.6 - 2478 + 53.7 (Stage 2)	300.4			2470 + 61.3 - 2477 + 30.74 (PRE-Stage 1) LT	410.31	
	2470 + 97.4 - 2476 + 72.5 (Stage 2)	193.2			2470 + 91.4 - 2476 + 82.52 (Stage 1) RT	293.3	
	2516 + 93.1 - 2524 + 17.4 (Stage 1)	242.3			2475 + 13 - 2475 + 73.5 (Stage 2) LT	20.2	
	2518 + 78.3 - 2522 + 93.4 (Stage 1)	142.0			2472 + 54.3 - 2472 + 95.7 (Stage 2) LT	45.92	
	2517 + 87.9 - 2524 + 45.8 (Stage 2)	220.0			Total=	769.73	
	2519 + 05.9 - 2522 + 45.0 (Stage 2)	136.7		Z0023600	Filling Existing Culvert	Each	
	2468 + 43.2	29.6			Location		
	2478 + 63.7	27.5			2473 + 27.2	1	
	2516 + 83.1	26			Total=	1	
	2524 + 45.8	27.2					
	Total=	1873.2		Z0030250	Impact Attenuators, Temporary (Non-Directive), Test Level 3	Each	
70400100	Temporary Concrete Barrier	Foot			Location		
	Location				2518 + 67.0 & 2523 + 04.9 (Stage 1)	2	
	2470 + 42.3 - 2476 + 79.0 (Stage 1)	637.5			2470 + 32.1 & 2476 + 90.5 (Stage 1)	2	
	2518 + 67.4 - 2523 + 04.2 (Stage 1)	437.5			Total=	4	
	Total=	1075		Z0030350	Impact Attenuators, Relocate (Non-Directive), Test Level 3	Each	
					Location		
70400200	Relocate Temporary Concrete Barrier	Foot			2518 + 92.0 & 2522 + 80.0 (Stage 2)	2	
	Location				2470 + 51.1 & 2476 + 83.8 (Stage 2)	2	
	2470 + 61.4 - 2476 + 73.3 (Stage 2)	612.5			Total=	2	
	2518 + 92.4 - 2522 + 79.3 (Stage 2)	387.5					
	Total=	1000					
78001110	Paint Pavement Marking - Line 4"	Foot					
	Location						
	2469 + 54.6 - 2478 + 53.7 LT	899.0					
	2469 + 54.6 - 2478 + 53.7 Centerline	225.0					
	2468 + 53.2 - 2477 + 80.8 RT	928.0					
	2517 + 22.3 - 2524 + 00 Centerline	170					
	2517 + 22.3 - 2523 + 32 RT	610					
	2518 + 05.2 - 2524 + 79.1 LT	674					
	Total=	7012	2 Applications				

2 REVISED SHEET 2-24-09

FILE NAME =	USER NAME = fordjd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL 251	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
ca:\pwork\pwork\fordjd\dms33877\0254487-sht-schedule.dgn		DRAWN -	REVISED -			1177	111T	LASALLE	59	17		
PLOT SCALE = 50.0000 ' / IN.		CHECKED -	REVISED -			CONTRACT NO. 64A07						
PLOT DATE = Fri Feb 20 12:00:48 2009		DATE -	REVISED -			SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.