

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	URBAN		I000-2A		Y007	
			TOTAL QUANTITY	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE (SN 101-1079)		
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	340	340				
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	85	85				
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	2,480	2,480				
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	19	19				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	29,009	29,009				
44000196	HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL	SQ YD	512	512				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	200	200				
44002224	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 6"	SQ YD	1,011	1,011				
44003100	MEDIAN REMOVAL	SQ FT	25,651	25,651				
44200120	PAVEMENT PATCHING, TYPE II, 10 INCH	SQ YD	131	131				
44200124	PAVEMENT PATCHING, TYPE III, 10 INCH	SQ YD	40	40				
44201359	CLASS C PATCHES, TYPE IV, 10 INCH	SQ YD	434	434				
48101200	AGGREGATE SHOULDERS, TYPE B	TON	84	84				
48203023	HOT-MIX ASPHALT SHOULDERS, 6 1/2"	SQ YD	1,017	1,017				
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1				1	
50104400	CONCRETE HEADWALL REMOVAL	EACH	4	4				
51500100	NAME PLATES	EACH	1				1	
54001001	BOX CULVERT END SECTION, CULVERT NO. 1	EACH	2				2	
54011204	PRECAST CONCRETE BOX CULVERT 12' X 4'	FOOT	204				204	
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	56	56				