

SCHEDULE OF QUANTITIES

550A0410 STORM SEWERS, CLASS A, TYPE 2 24"

<u>FOOT</u>	<u>LOCATION</u>
	US BUS 20
15	Sta 73+ 83 - 73+ 98 RT
15	TOTAL

61100500 EXPLORATION TRENCH 52" DEPTH

<u>FOOT</u>	<u>LOCATION</u>
	US BUS 20
10	As Needed & Directed by the Resident
10	TOTAL

66700305 PERMANENT SURVEY MARKERS, TYPE II

<u>EACH</u>	<u>LOCATION</u>
	US BUS 20
1	As Directed by the Resident and Coordination with Surveys
1	TOTAL

60600095 CLASS SI CONCRETE (OUTLET)

<u>CU YD</u>	<u>LOCATION</u>
	US BUS 20
3.5	Sta 74+ 08 - 74+ 32 RT
3.5	TOTAL

61133100 FIELD TILE JUNCTION VAULTS, 2' DIA.

<u>EACH</u>	<u>LOCATION</u>
	US BUS 20
1	As Needed & Directed by the Resident
1	TOTAL

70300100 SHORT-TERM PAVEMENT MARKING

<u>FOOT</u>	<u>LOCATION</u>
	US BUS 20
1,816	Sta 37+ 65 - 83+ 00 LT - White Skip Dash - 4 Appl.
1,816	Sta 37+ 65 - 83+ 00 RT - White Skip Dash - 4 Appl.
92	Sta 62+ 56 - 74+ 00 RT - Yellow Shoulder Stripes - 2 Appl.
3,724	TOTAL

60605000 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6,24

<u>FOOT</u>	<u>LOCATION</u>
	US BUS 20
60	Sta 73+ 40 - 74+ 00 LT
200	As Needed & Directed by the Resident
260	TOTAL

63200310 GUARDRAIL REMOVAL

<u>FOOT</u>	<u>LOCATION</u>
	US BUS 20
137.5	Sta 72 + 67 - 74 + 05 RT
137.5	TOTAL

70300520 PAVEMENT MARKING TAPE, TYPE III 4"

<u>FOOT</u>	<u>LOCATION</u>
	US BUS 20
2,582	Sta 54+ 40 - 80+ 20 Stage 2 - EB EOP
2,340	Sta 67+ 80 - 91+ 20 Stage 3 - WB EOP
4,922	White Total

60618300 CONCRETE MEDIAN SURFACE, 4 INCH

<u>SQ FT</u>	<u>LOCATION</u>
	US BUS 20
1,800	Sta 62 + 56 - 64 + 00
8,338	Sta 64 + 73 - 72 + 02
11,221	Sta 72 + 75 - 82 + 73
21,359	TOTAL

63500105 DELINEATORS

<u>EACH</u>	<u>LOCATION</u>
	US BUS 20
2	Sta 73 + 70 LT & RT Culvert
2	TOTAL

1,922	Sta 61+ 00 - 80+ 20	Stage 2 - EB EOP
2,360	Sta 67+ 60 - 91+ 20	Stage 2 - WB EOP
2,990	Sta 50+ 50 - 80+ 40	Stage 3 - EB EOP
1,572	Sta 67+ 80 - 83+ 50	Stage 3 - WB EOP
8,844	Yellow Total	
13,766	TOTAL	

60618750 CONCRETE MEDIAN, TYPE M-4.06

<u>SQ FT</u>	<u>LOCATION</u>
	US BUS 20
45	Sta 64 + 00 - 64 + 07
45	Sta 64 + 66 - 64 + 73
45	Sta 72 + 02 - 72 + 09
45	Sta 72 + 68 - 72 + 75
45	Sta 82 + 73 - 82 + 80
225	TOTAL

66600105 FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS

<u>EACH</u>	<u>LOCATION</u>
	US BUS 20
1	Sta 68 + 00 RT
1	Sta 69 + 00 RT
1	Sta 70 + 98 LT
1	Sta 71 + 00 RT
1	Sta 72 + 00 RT
1	Sta 73 + 47 LT
1	Sta 74 + 00 RT
1	Sta 74 + 25 LT
1	Sta 75 + 00 LT
1	Sta 76 + 00 RT
10	TOTAL

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

<u>SQ FT</u>	<u>LOCATION</u>
	US BUS 20
151.3	Sta 37+ 65 - 83+ 00 Removal of Surface Skip Dash
151.3	Sta 37+ 65 - 83+ 00 Removal of Surface Skip Dash
15.3	Sta 62+ 56 - 74+ 00 Removal of Surface Shoulder Stripe
860.7	Sta 54+ 40 - 80+ 20 Removal of Stage 2 Type III Tape
640.7	Sta 61+ 00 - 80+ 20 Removal of Stage 2 Type III Tape
786.7	Sta 67+ 60 - 91+ 20 Removal of Stage 2 Type III Tape
780.0	Sta 67+ 80 - 91+ 20 Removal of Stage 3 Type III Tape
996.7	Sta 50+ 50 - 80+ 40 Removal of Stage 3 Type III Tape
524.0	Sta 67+ 80 - 83+ 50 Removal of Stage 3 Type III Tape
4,906.7	TOTAL