

SCHEDULE OF QUANTITIES

Z0005400 BREAKER-RUN CRUSHED STONE

<u>TON</u>	<u>LOCATION</u>
	US BUS 20
434	Sta 73 + 70 (Depth = 18")
434	TOTAL

Z0030250 IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3

<u>EACH</u>	<u>LOCATION</u>
	US BUS 20
1	Sta 71 + 80 - 72 + 00 Stage 2
1	Sta 75 + 42 - 75 + 62 Stage 2
2	TOTAL

Z0024476 FLEXIBLE DELINEATOR MAINTENANCE

<u>EACH</u>	<u>LOCATION</u>
	US BUS 20
5	As Needed & Directed by the Resident
5	TOTAL

Z0030350 IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3

<u>EACH</u>	<u>LOCATION</u>
	US BUS 20
1	Sta 72 + 92 - 73 + 12 Stage 3
1	Sta 75 + 42 - 75 + 62 Stage 3
2	TOTAL

Z0028415 GEO TECHNICAL REINFORCEMENT

<u>SQ YD</u>	<u>LOCATION</u>
	US BUS 20
171	As Directed by the Resident (Full Depth Patches)
171	TOTAL

Z0028700 GRANULAR SUBGRADE REPLACEMENT

<u>CU YD</u>	<u>LOCATION</u>
	US BUS 20
29	As Directed by the Resident (Full Depth Patches)
29	TOTAL

Z0029001 GRATED CULVERT EXTENSION, NO. 1

<u>EACH</u>	<u>LOCATION</u>
	US BUS 20
2	Sta 73 + 70 RT
2	TOTAL

EARTHWORK SCHEDULE

LOCATION	EARTH EXC (CUT)	EARTH EXC ADJ SHRINK 25%	EMBANK (FILL)	EARTH WORK BALANCE WASTE (+) SHORTAGE (-)
	CU YD	CU YD	CU YD	CU YD
62 + 56 - 75 + 00	1202	902	229	673
TOTAL	1202	902	229	673