

SUMMARY OF QUANTITIES

			80% FED 20% STATE MINOR STRUCTURE Y007
CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
70106700	TEMPORARY RUMBLE STRIP	EACH	6
70300220	TEMPORARY PAVEMENT MARKING-LINE 4"	FOOT	1907
70300280	TEMPORARY PAVEMENT MARKING-LINE 24"	FOOT	24
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	731
70400100	TEMPORARY CONCRETE BARRIER	FOOT	387
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	312
* 78001110	PAINT PAVEMENT MARKING-LINE 4"	FOOT	3044
78300100	PAVEMENT MARKING REMOVAL	SQ FT	170
Z0005400	BREAKER-RUN CRUSHED STONE	TON	166
Z0013798	CONSTRUCTION LAYOUT	L SUM	1
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2
Z0064505	SECTION CORNER MARKERS	EACH	1
X4810100	TEMPORARY SHOULDERS	SQ YD	179
X7013015	TRAFFIC CONTROL FOR ROAD CLOSURE	L SUM	1
* A2006514	^{TREE,} QUERCUS BICOLOR (SWAMP WHITE OAK), 1-34" CALIPER, BALLED AND BURLAPPED	EACH	6

* SPECIALTY ITEMS