

SCHEDULE OF QUANTITIES

70400100 TEMPORARY CONCRETE BARRIER

FOOT	LOCATION	REMARK'S
387	775 + 86 TO 779 + 73	
387	TOTAL	

70400200 RELOCATE TEMPORARY CONCRETE BARRIER

FOOT	LOCATION	REMARK'S
312	776 + 23 TO 779 + 35	
312	TOTAL	

78001110 PAINT PAVEMENT MARKING—LINE 4"

FOOT	LOCATION	REMARK'S
360	774 + 30 TO 781 + 31	YELLOW 2 COATS
1402	774 + 30 TO 781 + 31 RT	WHITE 2 COATS
1282	774 + 30 TO 781 + 31 LT	WHITE 2 COATS, OMIT AT FROG POND ROAD
3044	TOTAL	

78300100 PAVEMENT MARKING REMOVAL

SQ FT	LOCATION	REMARK'S
109	776 + 16 TO 779 + 43 RT	STAGE 2
61	777 + 30 TO 779 + 14 LT	STAGE 3
170	TOTAL	

Z0005400 BREAKER—RUN CRUSHED STONE

TON	LOCATION	REMARK'S
166	777 + 76	109' X 10' UNDER BOX CULVERT (24 inch)
166	TOTAL	

Z0030250 IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3

EACH	LOCATION	REMARK'S
1	775 + 86	STAGE 2
1	779 + 73	STAGE 2
2	TOTAL	

Z0030350 IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3

EACH	LOCATION	REMARK'S
1	775 + 86	STAGE 3
1	779 + 73	STAGE 3
2	TOTAL	

Z0064505 SECTION CORNER MARKERS

EACH	LOCATION	REMARK'S
1	777 + 93.4 0.78' RT	
1	TOTAL	

X4810100 TEMPORARY SHOULDERS

SQ YD	LOCATION	REMARK'S
116	776 + 6 TO 779 + 53 RT	3' WIDE STAGE 2, to remain in when project is complete.
63	777 + 35 TO 779 + 24 LT	3' WIDE, STAGE 3, to remain in when project is complete.
179	TOTAL	