

# HMA SCHEDULE

LOCATION			PAVT		PAVEMENT AREA (SQ YD)	40600200	40600300	40600625	40600982	40600990	40603310		40800050	44000158	44000198	48101200	70300100	70301000
			LENGTH (FT.)	WIDTH (FT.)		BIT. PRIME 2 APPL (TON)	AGG. PRIME 1 APPL (TON)	LEVELING BINDER (MACHINE METHOD), N50 (TON)	HMA SURF REMOVAL BUTT JOINT (SQ YD)	TEMPORARY RAMP (SQ YD)	HMA SURF CRSE MIX "C", N50 1-1/2" (TON)	HMA SURF CRSE MIX "C", N50 2-1/4" (TON)	INCIDENTAL HOT MIX SURFACING (TON)	HMA SURFACE REMOVAL 2-1/4" (SQ YD)	HMA SURF REM VARIABLE DEPTH (SQ YD)	AGGREGATE SHOULDERS, TYPE B (TON)	SHORT TERM PAVEMENT MARKINGS (FT.)	WORK ZONE PAVE MARK REMOVAL (SQ FT)
STATIONING	DESCRIPTION		(FT.)	(FT.)	(SQ YD)	(TON)	(TON)	(TON)	(SQ YD)	(SQ YD)	(TON)	(TON)	(TON)	(SQ YD)	(SQ YD)	(TON)	(FT.)	(SQ FT)
308+45	TO	308 + 92	47	26	136	0.10	0.2	7.6			11.4	5.3					14.1	1.6
308+92	TO	309 + 76	84	26	243	0.16	0.4	13.6			20.4	4.7				5.3	25.2	2.8
309+76	TO	312 + 66	290	26	838	0.48	1.3	46.9			70.4					36.7	87.0	9.7
312+66	TO	313 + 60	94	26	272	0.16	0.4	15.2			22.8			135.8		11.9	28.2	3.1
313+60	TO	328 + 00	1440	26	4160	2.38	6.2	233.0			349.4			4160.0		182.2	432.0	48.0
328+00	TO	336 + 30	830	26	2398	1.37	3.6	134.3			201.4					105.0	249.0	27.7
336+30	TO	349 + 50	1320	26	3813	2.18	5.7	213.5			320.3			3813.3		167.0	396.0	44.0
349+50	TO	363 + 20	1370	26	3958	2.26	5.9	221.6			332.5			1978.9		173.4	411.0	45.7
363+20	TO	373 + 30	1010	26	2918	1.67	4.4	163.4			245.1			2917.8		127.8	303.0	33.7
373+30	TO	375 + 50	220	26	636	0.36	1.0	35.6			53.4			317.8		27.8	66.0	7.3
375+50	TO	386 + 08	1058	26	3056	1.75	4.6	171.2			256.7					133.9	317.4	35.3
386+08	TO	390 + 72	464	26	1340	1.00	2.0	75.1			112.6	52.0					139.2	15.5
390+72	TO	393 + 10	238	26	688	0.39	1.0	38.5			57.8					30.1	71.4	7.9
393+10	TO	395 + 90	280	26	809	0.46	1.2	45.3			67.9			404.4		35.4	84.0	9.3
395+90	TO	416 + 18	2028	26	5859	3.37	8.8	328.1			492.1			5858.7		256.6	608.4	67.6
416+18	TO	416 + 70	52	26	150	0.09	0.2	8.4			12.6	5.8		150.2			15.6	1.7
416+70	TO	417 + 15	45	32.5	163	0.09	0.2	9.1			13.7							
417+15	TO	417 + 68	53	26	153	0.11	0.2	8.6			12.9	5.9		153.1			15.9	1.8
417+68	TO	418 + 33	65	26	188	0.13	0.3	10.5			15.8	7.3		93.9			19.5	2.2
418+33	TO	424 + 60	627	26	1811	1.04	2.7	101.4			152.2			905.7		79.3	188.1	20.9
424+60	TO	449 + 00	2440	26	7049	4.03	10.6	394.7			592.1			7048.9		308.8	732.0	81.3
449+00	TO	473 + 70	2470	26	7136	4.08	10.7	399.6			599.4			3567.8		312.6	741.0	82.3
473+70	TO	479 + 64	594	26	1716	0.98	2.6	96.1			144.1					75.2	178.2	19.8
479+64	TO	489 + 36	972	26	2808	2.10	4.2	157.2			235.9	108.9				295.2	291.6	32.4
489+36	TO	491 + 70	234	26	676	0.39	1.0	37.9			56.8					29.6	70.2	7.8
491+70	TO	496 + 94	524	26.5	1543	0.88	2.3	86.4			129.6		1542.9			33.2	157.2	17.5
496+94	TO	501 + 30	436	26	1260	0.72	1.9	70.5			105.8			629.8		55.2	130.8	14.5
501+30	TO	504 + 70	340	26	982	0.56	1.5	55.0			82.5					43.0	102.0	11.3
504+70	TO	508 + 00	330	26	953	0.55	1.4	53.4			80.1			476.7		41.8	99.0	11.0
508+00	TO	516 + 30	830	26	2398	1.37	3.6	134.3			201.4					105.0	249.0	27.7
516+30	TO	525 + 25	895	26	2586	1.48	3.9	144.8			217.2			1292.8		113.3	268.5	29.8
525+25	TO	541 + 03	1578	26	4559	2.61	6.8	255.3			382.9					199.7	473.4	52.6
541+03	TO	550 + 02	899	26.5	2647	1.51	4.0	148.2			222.4		2647.1			56.9	269.7	30.0
550+02	TO	551 + 63	161	26	465	0.35	0.7	26.0	72.2	12.1	39.1	18.0					48.3	5.4
551+63	TO	552 + 76	113															
552+76	TO	554 + 30	154	26	445	0.33	0.7	24.9	72.2	12.1	37.4	17.2					46.2	5.1
554+30	TO	555 + 00	70	26.5	206	0.14	0.3	11.5			17.3	3.9	206.1				21.0	2.3
555+00	TO	561 + 12	612	26.5	1802	1.03	2.7	100.9			151.4		1802.0			38.7	183.6	20.4
561+12	TO	576 + 30	1518	26	4385	2.51	6.6	245.6			368.4			2192.7		192.1	455.4	50.6
576+30	TO	578 + 00	170	26	491	0.28	0.7	27.5			41.3					21.5	51.0	5.7
WEST LOTT ROAD			57	22	151	0.04	0.2		44.0	12.2								
EAST BUTZ ROAD			65	22	163	0.05	0.2		44.0	12.2								
WEST HERSHEY HIGHWAY			27	22	108	0.03	0.2		44.0	12.2								
EAST HERSHEY HIGHWAY			22	22	97	0.03	0.1		44.0	12.2								
WEST SABIN CHURCH RD			27	24	117	0.03	0.2		48.0	13.3								
EAST SABIN CHURCH RD			27	24	156	0.04	0.2		48.0	13.3								
WEST LORAN ROAD			22	54	215	0.06	0.3		108.0	30.0								
EAST LORAN ROAD			27	22	116	0.03	0.2		44.0	12.2								

FILE NAME =	USER NAME = dssdd	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>IL 73</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ca\pvr\work\p\10101\DOSSDD\dms33571\082970vr.dgn		DRAWN -	REVISED -			654	*	STEPHENSON	89	20	
		CHECKED -	REVISED -			CONTRACT NO. 64C91					
		DATE -	REVISED -			ILLINOIS FED. AID PROJECT					