

# ENTRANCE SCHEDULE

40600200 40800050

STATION	TYPE, RT/LT	REMARKS	EXISTING SURFACE TYPE	FLARE WIDTH (FT)	THROAT WIDTH (FT)	LENGTH (FT)	TOTAL AREA (SQ YD)	BIT PRIME (TONS)	INCIDEN BIT SURF (TONS)
222+64	CER		BIT	45	45	6	30.0	0.01	4.2
228+00	PER		BIT	20	20	6	13.3	0.00	1.9
280+15	CEL		BIT	33	21	21	63.0	0.02	8.8
327+24	PEL		BIT	36	15	21	59.5	0.02	8.3
327+24	MBR		BIT	110	20	6	43.3	0.01	6.1
340+66	PER		AGG	40	24	18	64.0	0.09	9.0
341+80	PER		BIT	36	12	18	48.0	0.01	6.7
360+46	FER		BIT	36	20	18	56.0	0.02	7.8
362+24	PE/MBR		BIT	90	15	18	105.0	0.03	14.7
366+31	MBR		BIT	110	20	6	43.3	0.01	6.1
370+37	PE/MBR		BIT	90	15	18	105.0	0.03	14.7
375+43	PER		BIT	24	12	18	36.0	0.01	5.0
376+38	PE/MBR		BIT	85	15	18	100.0	0.03	14.0
377+75	PE/MBR		BIT	75	12	18	87.0	0.02	12.2
429+43	PE/MBR		AGG	95	12	18	107.0	0.15	15.0
458+69	PE/MBR		BIT	95	12	18	107.0	0.03	15.0
471+41	PEL		BIT	36	20	18	56.0	0.02	7.8
483+69	FEL	RECONSTRUCTED FE	GRASS	54	24	41.5	141.9	0.00	0.0
484+66	FER	RECONSTRUCTED FE	GRASS	54	24	58	183.7	0.00	0.0
487+18	FER	RECONSTRUCTED FE	GRASS	54	24	48.7	165.0	0.00	0.0
490+00	PE/MBR		BIT	90	12	28	158.7	0.05	22.2
492+50	MBR		BIT	110	20	6	43.3	0.01	6.1
505+96	PEL		AGG	36	15	18	51.0	0.07	7.1
505+96	PER		BIT	78	15	18	93.0	0.03	13.0
511+66	PEL		BIT	30	12	18	42.0	0.01	5.9
512+64	PEL		BIT	30	12	18	42.0	0.01	5.9
537+36	PEL		BIT	30	12	18	42.0	0.01	5.9
538+10	MBR		BIT	65	20	6	28.3	0.01	4.0
543+76	PE/MBR		BIT	95	12	21	124.8	0.04	17.5
546+18	FEL		BIT	54	21	18	75.0	0.02	10.5
555+77	FEL		BIT	54	21	18	75.0	0.02	10.5
559+05	PER		BIT	36	15	15	42.5	0.01	6.0
560+27	PE/MBR		BIT	75	21	18	96.0	0.03	13.4
567+35	MBR		BIT	100	20	6	40.0	0.01	5.6
567+63	PEL		BIT	43	21	15	53.3	0.02	7.5
574+20	CEL		BIT	59	28	15	72.5	0.02	10.2
576+91	PER		BIT	24	12	18	36.0	0.01	5.0
<b>TOTALS</b>								<b>2.06</b>	<b>593.8</b>

FILE NAME =	USER NAME = dssdd	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>IL 73</b>				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
et\pwwork\PWIDOT\DOSSDD\dms33571\d8297evr.dgn		DRAWN -	REVISED -						654	*	STEPHENSON	89	30
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -						CONTRACT NO. 64C91				
PLOT DATE = Wed Sep 24 07:52:45 2008		DATE -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT		