

# SCHEDULE OF QUANTITIES

20200100 EARTH EXCAVATION

CULYD	LOCATION	OFFSET	REMARKS
1096.0	479+50 TO 489+50	LT	Stage I
2231.0	479+50 TO 489+50	RT	Stage II
3330.0	TOTAL		

28000250 TEMPORARY EROSION CONTROL SEEDING

LB	LOCATION	OFFSET	REMARKS
450.0	479+50 TO 487+50	VAR	
450.0	TOTAL		

20201200 REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL

CULYD	LOCATION	OFFSET	REMARKS
145.0	486+64	50' LT TO 50' RT	
145.0	TOTAL		

28000300 TEMPORARY DITCH CHECK

EACH	LOCATION	OFFSET	REMARKS
1	480+50	30' LT	
1	481+25	29' LT	
1	482+75	40' LT	
1	484+00	40' LT	
1	485+25	44' LT	
1	486+50	50' LT	
1	486+75	47' LT	
1	487+10	45' LT	
1	487+45	41' LT	
1	487+80	36' LT	
1	488+15	35' LT	
1	488+50	33' LT	
1	488+85	30' LT	
1	480+00	30' RT	
1	481+00	33' RT	
1	482+00	35' RT	
1	483+50	40' RT	
1	485+00	44' RT	
1	486+50	52' RT	
1	486+75	48' RT	
1	487+80	36' RT	
1	488+15	34' RT	
1	488+50	32' RT	
1	488+85	30' RT	
24	TOTAL		

25000100 SEEDING, CLASS 1

ACRE	LOCATION	OFFSET	REMARKS
0.25	487+32 TO 489+50	RT	
0.25	TOTAL		

25000210 SEEDING, CLASS 2A

ACRE	LOCATION	OFFSET	REMARKS
0.50	479+64 TO 487+08	RT	
0.25	479+64 TO 489+50	LT	
0.75	TOTAL		

25000310 SEEDING, CLASS 4

ACRE	LOCATION	OFFSET	REMARKS
0.25	479+64 TO 487+08	RT	
0.25	479+64 TO 498+50	LT	
0.50	TOTAL		

25000750 MOWING

ACRE	LOCATION	OFFSET	REMARKS
1.00	479+64 TO 489+50	LT & RT	MOW CL 1 AND CL 2A SEEDING.
1.00	TOTAL		

28000400 PERIMETER EROSION BARRIER

FOOT	LOCATION	OFFSET	REMARKS
478.3	479+64 TO 484+53	RT	
475.8	484+76 TO 498+50	RT	
383.7	479+64 TO 483+58	LT	
118.2	483+81 TO 485+00	LT	
453.3	485+00 TO 489+50	LT	
1909.3	TOTAL		

25100630 EROSION CONTROL BLANKET

SQ YD	LOCATION	OFFSET	REMARKS
659.6	479+64 TO 483+58	LT	
448.4	483+81 TO 485+00	LT	
678.0	485+00 TO 486+64	LT	
14.6	486+64	LT	OVER CULVERT
687.6	486+64 TO 489+50	LT	
1441.3	479+64 TO 484+58	RT	
106.8	484+77 TO 485+00	RT	
788.7	485+00 TO 487+08	RT	
504.6	487+32 TO 489+50	RT	
5329.6	TOTAL		

28000500 INLET AND PIPE PROTECTION

EACH	LOCATION	OFFSET	REMARKS
1	483+45	39' LT	
1	484+30	43' RT	
1	486+84	50' RT	
1	487+45	44' RT	
4	TOTAL		

25100900 TURF REINFORCEMENT MAT

SQ YD	LOCATION	OFFSET	REMARKS
351.5	486+00 TO 487+06	RT	PLACE FROM DITCH BOTTOM TO OUTSIDE EDGE
351.5	TOTAL		

28100107 STONE RIPRAP, CLASS A4

SQ YD	LOCATION	OFFSET	REMARKS
33.3	486+63	50' RT	30' X 10'
35.6	486+63	50' LT	16' X 20'
68.9	TOTAL		

FILE NAME =	USER NAME = dosadd	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>IL 73</b>				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
et\pwwork\PWIDOT\DOSSDD\dms33571\d029670vr.dgn		DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	654	*	STEPHENSON	89	31
		CHECKED -	REVISED -						CONTRACT NO. 64C91						
		DATE = Wed Sep 24 07:41:59 2008	REVISED -						ILLINOIS FED. AID PROJECT						