

SCHEDULE OF QUANTITIES

54215553 METAL END SECTIONS, 18"

EACH	LOCATION	OFFSET	REMARKS
2.0	483+68	39' LT	
2.0	484+66	43' RT	
2.0	487+18	44' RT	
6.0	TOTAL		

60255500 MANHOLES TO BE ADJUSTED

EACH	LOCATION	OFFSET	REMARKS
1	242+00	25' LT	STORM
1	242+03	15' RT	SANITARY
1	242+20	28' LT	STORM
1	263+65	20' RT	STORM
4	TOTAL		

60265700 VALVE VAULTS TO BE ADJUSTED

EACH	LOCATION	OFFSET	REMARKS
2	226+68	21' LT	WALGREN ROAD
1	242+10	28' LT	SOUTH STREET
1	242+13	25' LT	SOUTH STREET
1	242+16	25' LT	SOUTH STREET
1	242+32	18' RT	SOUTH STREET
1	246+24	17' RT	DEVORE STREET
1	246+25	21' RT	DEVORE STREET
1	246+27	16' LT	DEVORE STREET
1	246+28	17' LT	DEVORE STREET
1	246+29	16' LT	DEVORE STREET
1	246+35	17' RT	DEVORE STREET
1	246+55	26' LT	
1	249+45	26' LT	
1	251+73	17' LT	NORTH STREET
1	251+97	20' RT	NORTH STREET
1	252+31	20' RT	NORTH STREET
1	252+34	21' RT	NORTH STREET
1	252+36	20' RT	NORTH STREET
1	252+39	26' LT	
1	252+90	19' LT	
21	TOTAL		

60265800 VALVE VAULTS TO BE ADJUSTED (SPECIAL)

EACH	LOCATION	OFFSET	REMARKS
1	251+77	17' LT	NORTH STREET
1	252+95	19' LT	
1	277+70	17' LT	GARFIELD ROAD
3	TOTAL		

61100500 EXPLORATION TRENCH 52" DEPTH

FOOT	LOCATION	OFFSET	REMARKS
600.0	482+00 TO 488+00	VAR. RT	
450.0	483+50 TO 488+00	VAR. LT	
1050.0	TOTAL		

61100605 MISCELLANEOUS CONCRETE

CU YD	LOCATION	OFFSET	REMARKS
1.0	486+63	VAR RT	HEADWALL FOR EXISTING 8" TILE OUTLETS
1.0	486+63	VAR RT	HEADWALL FOR EXISTING 8" TILE OUTLETS
1.9	TOTAL		

61101013 STORM SEWERS PROTECTED, CLASS A, 12"

FOOT	LOCATION	OFFSET	REMARKS
10	481+10	35' LT TO 45' RT	
94	VAR	VAR	ESTIMATED QUANTITY TO BE USED IF NECESSARY
104	TOTAL		

61133100 FIELD TILE JUNCTION VAULTS, 2' DIA.

EACH	LOCATION	OFFSET	REMARKS
1	481+10	35' LT	
3	VAR	VAR	ESTIMATED QUANTITY TO BE USED IF NECESSARY
4	TOTAL		

63200310 GUARDRAIL REMOVAL

FOOT	LOCATION	OFFSET	REMARKS
100	480+50 TO 481+50	RT	
100	480+50 TO 481+50	LT	
100	486+00 TO 487+00	RT	
100	486+14 TO 487+14	LT	
400	TOTAL		

63500105 DELINEATORS

EACH	LOCATION	OFFSET	REMARKS
1	98+38	20' LT	AR CULVERT
1	467+55	17' RT	AR CULVERT
1	486+58	33' RT	
1	486+68	33' LT	
4	TOTAL		

66411900 TEMPORARY FENCE

FOOT	LOCATION	OFFSET	REMARKS
378	486+00 TO 489+53	VAR	
378	TOTAL		

66600105 FURNISHING AND ERECTING RIGHT OF WAY MARKERS

EACH	LOCATION	OFFSET	REMARKS
1	479+75	35' LT	
1	480+50	45' LT	
1	482+50	45' LT	
1	484+50	70' LT	
1	486+50	70' LT	
1	489+00	45' LT	
1	489+50	35' LT	
1	489+54	41' RT	
1	487+00	75' RT	
1	486+75	100' RT	
1	486+35	100' RT	
1	486+00	75' RT	
1	484+25	75' RT	
1	480+50	45' RT	
1	479+75	35' RT	
15	TOTAL		

66700305 PERMANENT SURVEY MARKERS, TYPE II

EACH	LOCATION	OFFSET	REMARKS
3	AT CULVERT LOCATIONS		CONTACT SURVEY DEPARTMENT
3	TOTAL		