

SCHEDULE OF QUANTITIES

78001110 PAINT PAVEMENT MARKING - LINE 4"

FOOT	LOCATION	OFFSET	REMARKS
3,296	0+00 TO 16+48	CL	DOUBLE YELLOW
879	16+48 TO 23+51	CL	YELLOW, SKIP DASH NB, NO PASSING ZONE SB
122	23+51 TO 28+38	CL	YELLOW SKIP DASH
885	28+38 TO 35+46	CL	YELLOW, NO PASSING ZONE NB, SKIP DASH SB
1,384	35+46 TO 42+38	CL	DOUBLE YELLOW
1,153	42+38 TO 51+60	CL	YELLOW, SKIP DASH NB, NO PASSING ZONE SB
6,104	51+60 TO 82+12	CL	DOUBLE YELLOW
1,248	82+12 TO 92+10	CL	YELLOW, SKIP DASH NB, NO PASSING ZONE SB
280	92+10 TO 103+31	CL	YELLOW SKIP DASH
411	103+31 TO 106+60	CL	YELLOW, NO PASSING ZONE NB, SKIP DASH SB
1,626	106+60 TO 114+73	CL	DOUBLE YELLOW
1,169	114+73 TO 124+08	CL	YELLOW, SKIP DASH NB, NO PASSING ZONE SB
242	124+08 TO 133+75	CL	YELLOW SKIP DASH
913	133+75 TO 141+05	CL	YELLOW, NO PASSING ZONE NB, SKIP DASH SB
47	141+05 TO 142+94	CL	YELLOW SKIP DASH
851	142+94 TO 149+75	CL	YELLOW, SKIP DASH NB, NO PASSING ZONE SB
231	149+75 TO 158+97	CL	YELLOW SKIP DASH
1,009	158+97 TO 167+04	CL	YELLOW, NO PASSING ZONE NB, SKIP DASH SB
77	167+04 TO 170+12	CL	YELLOW SKIP DASH
455	170+12 TO 173+76	CL	YELLOW, NO PASSING ZONE NB, SKIP DASH SB
2,308	173+76 TO 185+30	CL	DOUBLE YELLOW
1,160	185+30 TO 194+58	CL	YELLOW, SKIP DASH NB, NO PASSING ZONE SB
92	194+58 TO 198+25	CL	YELLOW SKIP DASH
1,319	198+25 TO 208+80	CL	YELLOW, NO PASSING ZONE NB, SKIP DASH SB
1,260	208+80 TO 215+10	CL	DOUBLE YELLOW
549	215+10 TO 219+49	CL	YELLOW, SKIP DASH NB, NO PASSING ZONE SB
2,361	219+49 TO 313+93	CL	YELLOW SKIP DASH
1,190	313+93 TO 323+45	CL	YELLOW, NO PASSING ZONE NB, SKIP DASH SB
2,934	323+45 TO 338+12	CL	DOUBLE YELLOW
1,154	338+12 TO 347+35	CL	YELLOW, SKIP DASH NB, NO PASSING ZONE SB
171	347+35 TO 354+19	CL	YELLOW SKIP DASH
1,459	354+19 TO 365+86	CL	YELLOW, NO PASSING ZONE NB, SKIP DASH SB
1,143	365+86 TO 375+00	CL	YELLOW, SKIP DASH NB, NO PASSING ZONE SB
438	375+00 TO 392+50	CL	YELLOW SKIP DASH
1,346	392+50 TO 403+27	CL	YELLOW, NO PASSING ZONE NB, SKIP DASH SB
218	403+27 TO 404+36	CL	DOUBLE YELLOW
1,279	404+36 TO 414+59	CL	YELLOW, SKIP DASH NB, NO PASSING ZONE SB
124	414+59 TO 419+53	CL	YELLOW SKIP DASH
1,184	419+53 TO 429+00	CL	YELLOW, NO PASSING ZONE NB, SKIP DASH SB
200	429+00 TO 430+00	CL	DOUBLE YELLOW
946	430+00 TO 437+57	CL	YELLOW, SKIP DASH NB, NO PASSING ZONE SB
88	437+57 TO 441+10	CL	YELLOW SKIP DASH
1,296	441+10 TO 451+47	CL	YELLOW, NO PASSING ZONE NB, SKIP DASH SB
4,554	451+47 TO 474+24	CL	DOUBLE YELLOW
750	474+24 TO 480+24	CL	YELLOW, SKIP DASH NB, NO PASSING ZONE SB
86	480+24 TO 483+69	CL	YELLOW SKIP DASH
1,176	483+69 TO 493+10	CL	YELLOW, NO PASSING ZONE NB, SKIP DASH SB
472	493+10 TO 495+46	CL	DOUBLE YELLOW
1,103	495+46 TO 504+28	CL	YELLOW, SKIP DASH NB, NO PASSING ZONE SB
86	504+28 TO 507+70	CL	YELLOW SKIP DASH
803	507+70 TO 514+12	CL	YELLOW, NO PASSING ZONE NB, SKIP DASH SB
5,196	514+12 TO 540+10	CL	DOUBLE YELLOW
1,379	540+10 TO 551+13	CL	YELLOW, SKIP DASH NB, NO PASSING ZONE SB
1,496	551+13 TO 563+10	CL	YELLOW, NO PASSING ZONE NB, SKIP DASH SB
2,980	563+10 TO 578+00	CL	DOUBLE YELLOW
24,174	0+00 TO 241+74	12' LT	WHITE EDGE LINE
32,435	253+65 TO 578+00	12' LT	WHITE EDGE LINE
24,174	0+00 TO 241+74	12' RT	WHITE EDGE LINE
32,435	253+65 TO 578+00	12' RT	WHITE EDGE LINE
179,895	SUBTOTAL		
224	241+74 TO 253+65	RT	WHITE PARKING LINES
228	241+74 TO 253+65	RT	YELLOW NO PARKING LINES (INCLUDING DIAGONALS)
224	241+74 TO 253+65	LT	WHITE PARKING LINES
548	241+74 TO 253+65	LT	YELLOW NO PARKING LINES (INCLUDING DIAGONALS)
181,119	SUBTOTAL		
X 2	TWO APPLICATIONS		
362,237	TOTAL		

ITEM NO	DESCRIPTION	EACH	LOCATION	OFFSET	REMARKS
78100100	RAISED REFLECTIVE PAVEMENT MARKER	723	0+00 TO 578+00	CL	TWO-WAY AMBER MARKERS, 80' SPACING
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	653	0+00 TO 578+00	CL	
XX001135	PAVEMENT PATCHING, SPECIAL	37.6	481+04 LT		
		37.6	481+04 RT		
		75.2	TOTAL		
X0322121	SHEET WATERPROOFING MEMBRANE SYSTEM	161.0	416+70 TO 417+16		STRUCTURE NO. 089-0053
Z0005400	BREAKER-RUN CRUSHED STONE	269	486+64	45' LT TO 45' RT	
Z0013798	CONSTRUCTION LAYOUT	1	479+64 TO 489+32	VAR	
Z0017100	DOWEL BARS	40	481+04	LT & RT	INSTALL PER 442101-07 BUT START 24" FROM EOP
		40	486+64	LT & RT	INSTALL PER 442101-07 BUT START 24" FROM EOP
		80	TOTAL		
Z0025500	FURNISHING AND INSTALLING PROPERTY MARKERS	2	486+00 TO 487+00		TO BE USED AS DIRECTED BY THE ENGINEER
Z0028415	GEO TECHNICAL REINFORCEMENT	494.0	0+00 TO 578+00		TO BE USED AS DIRECTED BY THE ENGINEER

FILE NAME =	USER NAME = dosedd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL 73	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
es:\pwork\PW1001\DOSSDD\dms33571\d02597\evr.dgn	DRAWN -	REVISD -	654			*	STEPHENSON	89	34	
PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -	CONTRACT NO. 64C91							
PLOT DATE = Wed Sep 24 07:43:53 2008	DATE -	REVISED -	ILLINOIS FED. AID PROJECT							
SCALE:		SHEET NO. OF SHEETS		STA. TO STA.		FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		