

PLAN	DATE
NO.	
BY	
DATE	
NO.	
BY	
DATE	
NO.	
BY	
DATE	
NO.	
BY	
DATE	
NO.	
BY	
DATE	
NO.	

PROFILE	DATE
NO.	
BY	
DATE	
NO.	
BY	
DATE	
NO.	
BY	
DATE	
NO.	
BY	
DATE	
NO.	
BY	
DATE	
NO.	

GUARDRAIL SCHEDULE										
LOCATION			SIDE	GUARDRAIL REMOVAL	STEEL PLATE BEAM GUARDRAIL ATTACHED TO STRUCTURES	STEEL PLATE BEAM GUARDRAIL TYPE A	TBT, TY1 (SP) TANGENT	TERMINAL MARKER DIRECT APPLIED	GUARDRAIL MARKER	
STATION	TO	STATION	LT/RT	(FT)	(FT)	(FT)	(EACH)	(EACH)	(EACH)	
48+67.50	TO	49+17.50	LT				1			
48+80.00	TO	49+30.00	RT				1			
48+67.50	TO	53+17.50	LT						18	
48+80.00	TO	52+42.50	RT						15	
49+17.50	TO	50+42.50	LT			125				
49+30.00	TO	50+42.50	RT			112.50				
49+30.42	TO	51+18.42	RT	188						
49+92.50	TO	51+80.50	LT	188						
50+42.50	TO	50+67.50	LT		25					
50+42.50	TO	50+67.50	RT		25					
50+67.50	TO	52+67.50	LT			200				
50+67.50	TO	51+92.50	RT			125				
51+92.50	TO	52+42.50	RT				1			
52+67.50	TO	53+17.50	LT				1			
APPLIED AT EACH FACE OF TBT								4		
TOTAL					376	50	562.50	4	4	33

PAVEMENT MARKING SCHEDULE					
LOCATION			SIDE	PAINT PAVEMENT MARKING-LINE 4"	PAINT PAVEMENT MARKING-LINE 6"
STATION	TO	STATION	LT/RT	WHITE (FT)	YELLOW SKIP DASH (FT)
46+10.00	TO	54+90.00	LT	880	
46+10.00	TO	54+90.00	RT	880	
46+10.00	TO	54+90.00	CL		220
TOTAL				1,760	220

EARTHWORK SCHEDULE				
STATION		SIDE	CUT VOLUME	FILL VOLUME
FROM	TO	LT/RT	(CU YD)	(CU YD)
47+00.00	54+00.00	LT	690.00	495.00
47+00.00	54+00.00	RT	490.00	320.00
TOTAL			1,180.00	815.00

MAINTENANCE OF TRAFFIC									
STAGE	LOCATION			SIDE	SHORT TERM PAVEMENT MARKING		TEMPORARY PAVEMENT MARKING-LINE 4"	TEMPORARY PAVEMENT MARKING-LINE 6"	WORK ZONE PAVEMENT MARKING REMOVAL
	STATION	TO	STATION		WIDTH (IN)	WHITE (FT)	WHITE (FT)	YELLOW (FT)	(SQ FT)
STAGE I	46+10.00	TO	54+90.00	LT			880		
	46+10.00	TO	54+90.00	RT			880		
	46+10.00	TO	54+90.00	CL				220	
	TOTAL				RT	24	12		24
STAGE II	47+45.00	TO	53+65.00	RT	4	620			207
	48+60.00	TO	52+50.00	LT	4	390			130
	TOTAL				LT	24	12		24
	47+45.00	TO	53+65.00	LT	4	620			207
48+60.00	TO	52+50.00	RT	4	390			130	
TOTAL						2,044	1,760	220	722

WOVEN WIRE FENCE SCHEDULE						
LOCATION			SIDE	WOVEN WIRE FENCE REMOVAL	WOVEN WIRE FENCE, 4'	TEMPORARY FENCE
STATION	TO	STATION	LT/RT	(FT)	(FT)	(FT)
47+00.00	TO	48+21.54	RT	122	122	122
48+80.14	TO	49+35.12	RT	55		
48+80.14	TO	50+37.06	RT		157	157
49+82.22	TO	50+25.86	RT	44		
50+86.32	TO	51+60.23	RT	74		
50+86.32	TO	51+64.07	RT		78	78
TOTAL				295	357	357

RIGHT-OF-WAY MARKERS	
LOCATION	EACH
STATION	
46+75.00, 30' LT	1
47+50.00, 45' LT	1
50+00.00, 45' LT	1
50+25.00, 40' LT	1
53+00.00, 40' LT	1
54+00.00, 29.07' LT	1
47+00.00, 30' RT	1
47+50.00, 35' RT	1
51+00.00, 35' RT	1
51+50.00, 40' RT	1
53+00.00, 40' RT	1
54+00.00, 31.10' RT	1
TOTAL	12

TEMPORARY BRIDGE TRAFFIC SIGNAL	
(EACH)	
1	
TOTAL	1

TREE REMOVAL (6 TO 15 UNITS DIAMETER)			
STATION	OFFSET (FT)	LT/RT	UNITS
49+77.81	34.0	RT	6
49+80.93	33.0	RT	8
50+09.07	33.0	RT	8
50+12.42	38.0	LT	10
51+25.12	33.0	RT	6
51+38.15	34.0	RT	8
51+98.63	32.0	RT	6
52+91.69	34.0	RT	6
TOTAL			58

TREE TRUNK PROTECTION			
STATION	OFFSET (FT)	LT/RT	EACH
47+73.55	35.0	RT	1
51+23.98	35.0	RT	1
51+75.46	38.0	RT	1
53+86.07	34.0	RT	1
53+86.07	34.0	RT	1
TOTAL			5

TREE PRUNING (1 TO 10 INCH DIAMETER)			
STATION	OFFSET (FT)	LT/RT	EACH
47+73.55	35.0	RT	1
51+23.98	35.0	RT	1
51+75.46	38.0	RT	1
53+86.07	34.0	RT	1
53+86.07	34.0	RT	1
TOTAL			5