

URBAN

90% FED.  
10% STATE

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	I000-2A	SFTY - 2A	Y080
40603570	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90	TON	6,755	6,755		
40701881	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 10"	SQ YD	4,269	4,269		
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	558	558		
42001200	PAVEMENT FABRIC	SQ YD	147	147		
42001300	PROTECTIVE COAT	SQ YD	2,301	558	1,743	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	112	112		
44000100	PAVEMENT REMOVAL	SQ YD	4,269	4,269		
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	124,563	124,563		
44004250	PAVED SHOULDER REMOVAL	SQ YD	315	315		
44200577	CLASS A PATCHES, TYPE II, 12 INCH	SQ YD	653	653		
44200581	CLASS A PATCHES, TYPE III, 12 INCH	SQ YD	238	238		
44200583	CLASS A PATCHES, TYPE IV, 12 INCH	SQ YD	499	499		
44201031	CLASS B PATCHES, TYPE II, 15 INCH	SQ YD	1,916	1,916		
44201035	CLASS B PATCHES, TYPE III, 15 INCH	SQ YD	59	59		
44201037	CLASS B PATCHES, TYPE IV, 15 INCH	SQ YD	88	88		
44213000	PATCHING REINFORCEMENT	SQ YD	1,389	1,389		
44213200	SAW CUTS	FOOT	13,596	13,596		
44300900	STRIP REFLECTIVE CRACK CONTROL TREATMENT SYSTEM A	FOOT	3,105	3,105		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2,312	2,312		
48203100	HOT-MIX ASPHALT SHOULDERS	TON	9,711	9,711		
50102400	CONCRETE REMOVAL	CU YD	33.6		33.6	
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	2		2	
50105220	PIPE CULVERT REMOVAL	FOOT	1,052	1,052		
50200100	STRUCTURE EXCAVATION	CU YD	124		124	
50300100	FLOOR DRAINS	EACH	16		16	

FILE NAME = 68602 PLANS .dgn  
USER NAME = taraja  
DESIGNED -  
DRAWN -  
PLOT SCALE = 40.0000' / IN.  
CHECKED -  
PLOT DATE = 12/12/2008  
DATE -

REVISIED -  
REVISIED -  
REVISIED -  
REVISIED -  
REVISIED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 2 OF 5 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	48(27RS-3; (27HB-5)I, I-1)	KNOX	104	5
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 68062	