

TRAFFIC CONTROL

| LOCATION             | TEMPORARY CONCRETE BARRIER | RELOCATE TEMPORARY CONCRETE BARRIER | TEMPORARY PAVEMENT MARKING (WHITE) | TEMPORARY PAVEMENT MARKING (YELLOW) | IMPACT ATTENUATOR TEMPORARY (FULLY REDIRECTIVE, NARROW), TL3 | IMPACT ATTENUATOR, RELOCATE (FULLY REDIRECTIVE), TL3 | TRAFFIC CONTROL & PROTECTION STD. 701306 | TRAFFIC CONTROL & PROTECTION STD. 701331 (SPECIAL) | POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50 (TEMP. PAV'T) | POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT 0.00038 TON/SQ. YD) |
|----------------------|----------------------------|-------------------------------------|------------------------------------|-------------------------------------|--------------------------------------------------------------|------------------------------------------------------|------------------------------------------|----------------------------------------------------|-----------------------------------------------------------------------|------------------------------------------------------------------|
|                      | FOOT                       |                                     |                                    |                                     | EACH                                                         |                                                      | L SUM                                    | EACH                                               | TON                                                                   |                                                                  |
| US 150 S.N. 090-0038 |                            |                                     |                                    |                                     |                                                              |                                                      | 1                                        |                                                    |                                                                       |                                                                  |
| PRESTAGE             |                            |                                     |                                    |                                     |                                                              |                                                      |                                          |                                                    | 192                                                                   | 0.2                                                              |
| STAGE 1              | 483                        |                                     | 1740                               | 1690                                | 2                                                            |                                                      |                                          | 1                                                  | 703                                                                   | 0.6                                                              |
| STAGE 2              | 196                        | 483                                 | 1840                               | 1790                                | 2                                                            | 2                                                    |                                          | 1                                                  |                                                                       |                                                                  |
| US 150 S.N. 090-0040 |                            |                                     |                                    |                                     |                                                              |                                                      |                                          |                                                    |                                                                       |                                                                  |
| PRESTAGE             |                            |                                     |                                    |                                     |                                                              |                                                      |                                          |                                                    | 324                                                                   | 0.3                                                              |
| STAGE 1              | 514                        |                                     | 1830                               | 1830                                | 2                                                            |                                                      |                                          | 1                                                  | 488                                                                   | 0.5                                                              |
| STAGE 2              | 492                        | 538                                 | 1830                               | 1830                                | 4                                                            | 2                                                    | 1                                        |                                                    |                                                                       |                                                                  |
| TOTAL                | 1685                       | 1021                                | 7240                               | 7140                                | 10                                                           | 4                                                    | 1                                        | 4                                                  | 1707                                                                  | 1.6                                                              |

AGGREGATE SHOULDERS, TYPE B 6"

| LOCATION             | SQ. YD. |
|----------------------|---------|
| US 150 S.N. 090-0038 |         |
| 47+35.00 47+59.41 LT | 21.7    |
| 47+59.41 48+36.93 LT | 43.1    |
| 49+20.78 50+34.40 LT | 63.3    |
| 50+34.40 50+80.51 LT | 41.0    |
| 50+80.51 50+92.14 LT | 5.7     |
| 47+35.00 47+45.52 RT | 5.8     |
| 47+82.53 48+11.74 RT | 17.1    |
| 48+11.74 49+20.12 RT | 60.2    |
| 50+05.34 50+99.38 RT | 54.0    |
| 50+99.38 52+05.00 RT | 93.8    |
| N EAST LANE          |         |
| 10+80.00 11+15.24 RT | 7.8     |
| 11+37.59 11+41.11 RT | 0.5     |
| 11+41.11 13+25.38 RT | 41.0    |
| 10+80.00 12+37.13 LT | 34.8    |
| 12+37.13 12+87.13 LT | 27.8    |
| 12+87.13 13+29.31 LT | 37.4    |
| 13+29.31 13+45.11 LT | 9.9     |
| CATHERINE STREET     |         |
| 50+28.91 50+56.68 LT | 8.8     |
| US 150 S.N. 090-0040 |         |
| 88+74.27 89+07.36 LT | 12.6    |
| 90+07.14 90+44.50 LT | 18.9    |
| 87+75.49 88+22.38 RT | 22.8    |
| 88+22.38 89+15.83 RT | 51.9    |
| 90+55.22 91+13.58 RT | 32.4    |
| 91+13.58 91+66.45 RT | 25.8    |
| WEDGES               |         |
| S.N. 090-0038        | 12.5    |
| N East Ln.           | 26.3    |
| Catherine St.        | 2.0     |
| S.N. 090-0040        | 8.8     |
| TOTAL                | 786     |

WORK ZONE

| LOCATION             | TRAFFIC CONTROL SURVEILLANCE | WORK ZONE PAVEMENT MARKING REMOVAL |
|----------------------|------------------------------|------------------------------------|
|                      | CAL DAY                      | SQ. FT.                            |
| US 150 S.N. 090-0038 |                              |                                    |
| STAGE 1              | 15                           | 651                                |
| STAGE 2              |                              | 1110                               |
| US 150 S.N. 090-0040 |                              |                                    |
| STAGE 1              | 15                           | 685                                |
| STAGE 2              |                              | 1103                               |
| TOTAL                | 30                           | 3549                               |

TERMINAL MARKER - DIRECT APPLIED BARRIER WALL MARKERS, TYPE B

| LOCATION             | EACH |
|----------------------|------|
| STATION TO STATION   | EACH |
| US 150 S.N. 090-0038 |      |
| 47+59.41 LT          | 1    |
| 48+11.74 RT          | 1    |
| 50+34.41 LT          | 1    |
| 50+99.38 RT          | 1    |
| US 150 S.N. 090-0040 |      |
| 88+22.38 RT          | 1    |
| 88+67.50 LT          | 1    |
| 90+60.25 RT          | 1    |
| TOTAL                | 7    |

| LOCATION             | EACH |
|----------------------|------|
| S.N. 090-0040        |      |
| 89+53.50 90+16.50 RT | 2    |
| 89+44.67 90+07.67 LT | 2    |
| TOTAL                | 4    |

PIPE DRAINS 12"

| LOCATION             | FOOT |
|----------------------|------|
| US 150 S.N. 090-0040 |      |
| NW CORNER            | 40   |
| SW CORNER            | 38   |
| TOTAL                | 78   |

COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12

| LOCATION    | FOOT |
|-------------|------|
| S. EAST LN. | 187  |
| TOTAL       | 187  |

TELESCOPING STEEL SIGN SUPPORT

| S.N. 090-0038                        | FOOT |
|--------------------------------------|------|
| SIGN / INTERSECTION                  | FOOT |
| "DEAD END" S EAST LN / SHADOWAY DR   | 15   |
| "STOP SIGN" N EAST LN / CATHERINE ST | 15   |
| "STOP SIGN" US 150 / CATHERINE ST    | 15   |
| TOTAL                                | 45   |

FILE NAME = E:\0102\Phase II\schedules.dgn

USER NAME = Plotted by flin  
 PLOT SCALE = 100.0000' / IN.  
 PLOT DATE = 10/15/2008

DESIGNED - ST  
 DRAWN - ST  
 CHECKED - FL  
 DATE - 12/2007

REVISED - ----  
 REVISED - ----  
 REVISED - ----  
 REVISED - ----

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES  
 US 150 OVER LITTLE FARM CREEK  
 SCALE: N/A SHEET NO. OF SHEETS STA. TO STA.

| F.A.U. RTE.                                   | SECTION                  | COUNTY   | TOTAL SHEETS | SHEET NO. |
|-----------------------------------------------|--------------------------|----------|--------------|-----------|
| 6757                                          | (105B) BR-2, (105B) BR-3 | TAZEWELL | 13           | 133       |
| CONTRACT NO. 68086                            |                          |          |              |           |
| FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT |                          |          |              |           |