

SUMMARY OF QUANTITIES

90% FEDERAL
10% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	90% FEDERAL 10% STATE	
				Henry County	Knox County
				ROADWAY I000 RURAL	ROADWAY I000 RURAL
64200105	SHOULDER RUMBLE STRIP	FOOT	140978	23272	117706
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4		4
67100100	MOBILIZATION	L SUM	1	0.2	0.8
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	3	2	1
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	0.2	0.8
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	0.2	0.8
<input checked="" type="checkbox"/> 70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1	0.2	0.8
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	2	8
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	29868	5008	24860
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	147464	29086	118378
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	17778	2981	14797
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	64	64	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	68	68	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3319	557	2762
<input type="checkbox"/> 78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	147464	29086	118378
<input type="checkbox"/> 78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	17778	2981	14797
<input type="checkbox"/> 78003140	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 8"	FOOT	64	64	
<input type="checkbox"/> 78003150	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 12"	FOOT	68	68	
<input type="checkbox"/> 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	912	172	740
<input checked="" type="checkbox"/> 78200410	GUARDRAIL MARKERS, TYPE A	EACH	82	33	49
<input type="checkbox"/> 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	16	5	11
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	277	172	105

SPECIALTY ITEMS

REVISED 2/18/09