

SCHEDULE OF QUANTITIES

TREE REMOVAL (6 TO 15 UNITS DIAMETER)	OFFSET	UNIT
STA 143+61	CL	6
STA 144+00	CL	7.5
STA 144+54	CL	7
STA 145+05.5	CL	8
STA 145+58	CL	7.5
STA 153+42.5	CL	7.5
STA 153+90	CL	6.7
STA 154+49	CL	6.7
STA 162+57.3	CL	7
STA 163+02	CL	6
STA 163+45	CL	6
STA 165+20	CL	6
STA 173+87	CL	6.2
STA 174+94	CL	6.2
STA 175+32	CL	6
STA 177+81	CL	8.5
STA 178+25	CL	7
STA 178+69	CL	6.5
STA 181+98	CL	7.6
STA 182+27.5	CL	6
STA 184+94.5	CL	6
STA 185+76	CL	7
TOTAL =		148.9

TREE REMOVAL (OVER 15 UNITS DIAMETER)	OFFSET FEET	UNIT
LT STA 162+89	51.5	29
LT STA 164+98.5	51	23
LT STA 165+15.5	50.5	26
LT STA 166+90.6	48.15	32
RT STA 176+59.5	47.3	35
RT STA 177+03.00	47.7	29
RT STA 177+27.00	46.8	30
RT STA 178+10	46	25
LT STA 192+62.4	57.3	21.5
TOTAL =		250.5

SPECIAL EXCAVATION	
LOCATION	CU YD
IL 8	
STA 132+00 TO 197+00	27,276
SIDEROADS	
CHERRY RD	189
HOLLY RD	83
STAHL AVE.	205
THEODORE ST.	152
CRESTLAWN DR.	165
BERRY ST.	93
ALBERT ST.	122
CARLSON AVE.	185
ESSER ST.	100
MASON AVE.	113
LOREN ST.	168
JAMES AVE.	169
DORIS ST.	172
MARY ST.	143
FLORIDA AVE.	149
BESS ST.	174
MASSACHUSETTS AVE.	114
LAKE ST.	172
SHERWOOD PARK	174
QUAIL TRAIL	130
OAKDALE RD.	189
MEADOW LANE	115
BRIARGATE (SOUTH)	133
BRIARGATE (NORTH)	118
TOTAL	30803.0

FURNISHED EXCAVATION	
LOCATION	CU YD
IL 8	
STA 132+00 TO 197+00	3,816
SIDEROADS	
CHERRY RD	1
HOLLY RD	13
STAHL AVE.	1
THEODORE ST.	1
CRESTLAWN DR.	4
BERRY ST.	8
ALBERT ST.	4
CARLSON AVE.	0
ESSER ST.	1
MASON AVE.	0
LOREN ST.	0
JAMES AVE.	0
DORIS ST.	0
MARY ST.	1
FLORIDA AVE.	2
BESS ST.	1
MASSACHUSETTS AVE.	3
LAKE ST.	0
SHERWOOD PARK	1
QUAIL TRAIL	3
OAKDALE RD.	14
MEADOW LANE	4
BRIARGATE (SOUTH)	6
BRIARGATE (NORTH)	0
TOTAL	3884

AGGREGATE FOR TEMPORARY ACCESS		TON
STAGE I		
LT STA 155+50	CE	15
LT STA 162+56.08	PE	12
LT STA 165+49.03	PE	12
LT STA 165+93.76	PE	12
LT STA 166+25.59	PE	12
LT STA 173+33.05	PE	12
LT STA 174+02.89	CE	15
LT STA 174+71.28	CE	15
12 SIDE STREETS		240
STAGE II		
RT STA 146+01.29	PE	12
RT STA 150+28.82	CE	15
RT STA 151+09.16	PE	12
RT STA 152+05.02	CE	15
RT STA 152+65.92	CE	15
RT STA 153+17.62	CE	15
RT STA 154+70.10	CE	15
RT STA 160+39.54	CE	15
RT STA 174+30.52	PE	12
RT STA 177+45.42	PE	12
RT STA 177+70.63	PE	12
12 SIDE STREETS		240
TOTAL		735

AGGREGATE SHOULDERS, TYPE B		TON
LOCATION		
RT STA. 132+08 TO RT STA 135+50		9.75
LT STA 132+30 TO LT STA 133+32		2.8
LT STA 133+72 TO LT STA 135+07		4.42
LT STA 135+35 TO LT STA 135+50		0.44
LT STA. 166+85 TO LT STA 194+74		5.59
TOTAL		23

STATION	STONE RIPRAP CLASS A4 SQYD	FILTER FABRIC SQYD
FROM STA. 142+26.68 TO STA. 143+00.71	57.91	57.91
TOTAL	57.91	57.91

TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE) 2" CALIPER, BALLED AND BURLAPPED		EACH
LOCATION		
STA 143+58.55 TO 145+36.79	PED. ISLAND	3
STA 153+32.29 TO 154+42.17	PED. ISLAND	2
STA 160+85.28 TO 161+84.18	PED. ISLAND	1
STA 174+51.72 TO 175+44.62	PED. ISLAND	2
STA 177+83.61 TO 178+71.08	PED. ISLAND	1
STA 184+97.84 TO 185+84.44	PED. ISLAND	2
TOTAL		11

STATION	HEAVY DUTY EROSION CONTROL BLANKET SQYD
FROM STA. TO STA.	LT / RT
132+99.83 TO 133+30.94	LT
133+71.70 TO 134+97.73	LT
135+25.00 TO 139+58.44	LT
135+49.09 TO 139+00.00	RT
140+04.83 TO 142+84.50	LT
142+99.42 TO 144+80.97	RT
TOTAL	1531.4

STATION	SEEDING CLASS 2A ACRE	MULCH METHOD 2 ACRE	NITROGEN FERTILIZER NUTRIENT POUND	PHOSPHORUS FERTILIZER NUTRIENT POUND	POTASSIUM FERTILIZER NUTRIENT POUND
FROM STA. TO STA.	LT / RT				
132+32.27 TO 133+42.19	LT	0.01	0.01	1.32	1.32
133+61.47 TO 135+07.65	LT	0.03	0.03	2.49	2.49
135+18.37 TO 139+73.00	LT	0.20	0.20	18.17	18.17
135+00.00 TO 139+65.00	RT	0.17	0.17	14.87	14.87
139+89.00 TO 146+22.75	LT	0.27	0.27	23.89	23.89
140+00.00 TO 145+93.00	RT	0.23	0.23	20.36	20.36
194+60.00 TO 196+71.00	RT	0.08	0.08	7.30	7.30
194+60.00 TO 195+02.98	LT	0.01	0.01	0.59	0.59
TOTAL=		1.0	1.0	89.0	89.0

FILE NAME = schedule.dgn	USER NAME = crespole	DESIGNED -	REVISED -
		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE. 399	SECTION 36 R-8	COUNTY TAZEWELL	TOTAL SHEETS 429	SHEET NO. 13
CONTRACT NO. 68258				
FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT				