

# **COMMITTMENTS**

No commitments have been made for this project.

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
I - 155	D4 BRG PNTG MTLZG 2008	TAZEWELL	11	2

# **GENERAL NOTES**

Cleaning, Painting & Metalizing of the existing steel shall be as specified in the special provision for **Field Thermal Spraying Metalizing". All beams, bearings, brackets and all other structural steel shall be cleaned per Near White Blast Cleaning – SSPC SP 10 according to following schedule.**

**Bridge No. 1 & 2 – All beams, bearings, brackets and all other structural steel within 5 feet ( as measured along the centerline of the beam) of either side of the deck joints.**

**All Meatlized areas shall be sealed with an IDOT approved sealer applied DFT of 1 to 2 mils.**

**The final finish coat for the exterior shall be according to the following schedule:**

**Bridge No. 1 & 2 – shall match the existing color of Blue ( Munsell No. 10B 3/6)**

**Removal of the PJS expansion seals shall be included in the cost of Preformed Joint Seal 3 1/2" & 4"**

**QP1 & QP2 ARE NOT REQUIREMENTS FOR THIS CONTRACT.**

**AIR MONITORS, will not be required for this project.**

**COMMITMENTS &  
GENERAL NOTES**