

LOCATION OF WORK:

FAI 74
RURAL
MCLEAN COUNTY
STA 1463+28.89 TO STA 297+86.57 (RAMP B)
90% FEDERAL
10% STATE
SFTY-3J

FAI 74
RURAL
MCLEAN COUNTY
STA 1463+28.89 TO STA 297+86.57 (RAMP B)
90% FEDERAL
10% STATE
SFTY-3N

CONSTRUCTION TYPE CODE:

CODE NO	ITEM	UNIT	TOTAL QUANTITY		
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1(SPECIAL) FLARED	EACH	32.0	32.0	0.0
63200310	GUARDRAIL REMOVAL	FOOT	11,329.0	11329.0	0.0
63400105	GUARD POSTS	EACH	100.0	0.0	100.0
63400205	GUARD POSTS REMOVAL	EACH	44.0	0.0	44.0
63500105	DELINEATORS	EACH	3.0	3.0	0.0
63500120	DELINEATOR REMOVAL	EACH	3.0	3.0	0.0
67100100	MOBILIZATION	L SUM	1.0	0.5	0.5
70100420	TRAFFIC CONTROL AND PROTECTION,STANDARD 701411	EACH	12.0	12.0	0.0
70100700	TRAFFIC CONTROL AND PROTECTION,STANDARD 701406	L SUM	1.0	0.5	0.5
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	166.0	166.0	0.0
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	32.0	32.0	0.0
X0931400	INLET BOXES TO BE ADJUSTED (SPECIAL)	EACH	1.0	0.0	1.0
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	28.0	14.0	14.0
Z0002005	ATTENUATOR BASE	SQ YD	1,016.0	0.0	1016.0
Z0013300	CONCRETE REMOVAL (SPECIAL)	SQ YD	451.0	0.0	451.0
Z0030150	IMPACT ATTENUATORS (NON-REDIRECTIVE),TEST LEVEL 3	EACH	20.0	0.0	20.0
Z0056220	SAND MODULE IMPACT ATTENUATOR TO BE REMOVED	EACH	211.0	0.0	211.0

* SPECIALTY ITEMS

FILE NAME :	USER NAME = cealockjd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\pwwork\CEALOCKJD\0101465\0570744-sht-500.dgn	DRAWN -	REVISED -	74						DSSAFETY-1	McLean	80	6	
PLOT SCALE = 40,0000 ' / IN.	CHECKED -	REVISED -	CONTRACT NO. 70744										
PLOT DATE = 12/11/2008	DATE -	REVISED -	SCALE:		SHEET NO.	OF	SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	