

PAVEMENT MARKING SCHEDULE CONTINUED

X7800620 X7800620 X7800630 78004230 78004240 78004250 78004250 78004280 78004200

STATION TO STATION	SIDE	DESCRIPTION	URETHANE PAVEMENT MARKING						PREFORMED PLASTIC PAVEMENT MARKING			
			LINE 5"		LINE 6"	LINE 6"	LINE 8"	LINE 12"		LINE 24"	LETTERS &	
			WHITE	YELLOW	WHITE	WHITE	WHITE	WHITE	YELLOW	WHITE	SYMBOLS	
									FOOT	SQ FT		
PAYSON ROAD (URBAN)												
12+50.0	19+12.6	RT	EDGE LINE	662.6								
12+50.0	16+35.5	LT	EDGE LINE	385.5								
12+50.0	13+52.3	CL	NO-PASSING		204.6							
13+52.3	16+64.9	LT & RT	CHANNELIZATION		625.2							
13+52.3	16+64.9	LT	CHANNELIZATION		625.2							
13+52.3	16+64.9	LT & RT	DIAGONALS					60.5				
16+93.1	18+32.3	LT	CHANNELIZATION		278.5							
16+93.1	18+32.3	LT	CHANNELIZATION		278.5							
16+93.1	18+32.3	LT	DIAGONALS					18.0				
17+19.5	18+23.8	LT	EDGE LINE	104.3								
18+23.8	19+39.9	LT	EDGE LINE	118.4								
18+27.5	19+42.5	CL	TURN LANE			115.0						
18+27.5	19+42.5	LT	LEFT TURN ARROWS (2)								31.2	
18+32.3	19+44.5	LT	NO-PASSING		224.4							
19+12.6	19+65.1	RT	EDGE LINE	69.6								
19+42.5	19+44.5	LT & RT	STOP BAR							31.0		
19+48.5	19+54.5	LT & RT	CROSS WALK				151.0					
35th STREET (URBAN)												
10+30.2	10+36.2	LT & RT	CROSS WALK				71.0					
10+40.2	10+42.2	LT	STOP BAR							12.0		
10+42.2	10+80.0	CL	NO-PASSING		75.6							
TOTALS				6610.9	10732.2	1377.4	356.0	765.3	249.5	609.0	138.5	342.9
USE				17344		1378	356	766	859		139	343

SIGNING SCHEDULE

72000100

X7800650

ROUTE	STATION	SIDE	FACING	SIGN * MUTCD	SIZE		SIGN PANEL TYPE 1	MESSAGE	# OF POSTS	TELESCOPING STEEL SIGN SUPPORT
					IN	IN				
FAS 1597 (IL 96)	2196+20	RT	EAST	M3-1	24	12	2.0	NORTH	1	19.0
				M1-100	24	24	4.0	IL 96		
				M6-1	21	15	2.2	ARROW		
	2198+20	RT	EAST	R3-I100	24	24	4.0	RT TURN LANE	1	18.0
				M6-2R	21	15	2.2	RT ARROW		
	2200+20	RT	EAST	W2-1	36	36	9.0	CROSS ROAD AHEAD	1	19.5
				W16-8	36	8	2.0	36TH STREET		
	2205+20	RT	SOUTHEAST	W12-1	36	36	9.0	DOUBLE ARROW	1	16.0
NORTHWEST				R5-1a	36	24	6.0	WRONG WAY		
2206+10	CL	WEST	R10-12	42	24	7.0	36TH STREET			
2206+33	RT	EAST	R3-1	30	30	6.3	NO RT TURN			
FAU 7830 (IL 96)	2205+11	CL	SOUTH	R10-12	54	24	9.0	PAYSON ROAD		
				R5-1	36	36	9.0	DO NOT ENTER	1	16.0
	2210+00	LT	NORTH	W4-1	36	36	9.0	MERGE		
				M3-3	24	12	2.0	SOUTH	1	19.0
	2209+25	RT	SOUTH	M1-100	24	24	4.0	IL 96		
				M6-1	21	15	2.2	ARROW		
				W4-2	36	36	9.0	LANE REDUCTION	1	18.8
2212+20	LT	NORTH	W2-1	36	36	9.0	CROSS ROAD AHEAD	1	19.5	
FAU 7817 (PAYSON RD)	19+35	CL	EAST	W16-8	36	8	2.0	PAYSON ROAD		
				R10-12	42	24	7.0	36TH STREET		
TR 64 (36TH STREET)	39+53	CL	NORTH	R3-1	30	30	6.3	NO RT TURN		
				R10-12	54	24	9.0	PAYSON ROAD		
RT TURN LANE	11+15	RT	NORTHWEST	R5-1a	36	24	6.0	WRONG WAY	1	16.8
				R5-1	36	36	9.0	DO NOT ENTER	1	17.8
TOTAL							146.2			180.4

FILE NAME =	et:\pw\work\PWIDOT\LAUGHLINRL\0114681\009SCHED01.dgn	DESIGNED -	REVISER -
USER NAME = laughlinr1		DRAWN -	REVISER -
PLOT SCALE = 40.0000 ' / IN.		CHECKED -	REVISER -
PLOT DATE = Dec-12-2008 02:50:37PM		DATE -	REVISER -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES			
SCALE: NONE	SHEET NO. 6	OF 7 SHEETS	STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	(11)N	ADAMS	117	14
* - FAS 1597 & FAU 7830			CONTRACT NO. 72817	
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				