

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY INTERSTATE MAINTENANCE 90% FEDERAL 10% STATE X031-2A
5421024	PIPE CULVERTS, CLASS C, TYPE 124" (TEMPORARY)	FOOT	828
54213459	END SECTIONS 24"	EACH	4
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	3
54215973	REINFORCED CONCRETE PIPE ELBOW 18"	EACH	1
54246205	INLET BOX, STANDARD 542526	EACH	2
54246405	INLET BOX, STANDARD 542531	EACH	1
54248510	CONCRETE COLLAR	CU YD	0.4
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	289
58700300	CONCRETE SEALER	SQ FT	2315
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	142
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	65
60108200	PIPE UNDERDRAINS 6" (SPECIAL)	FOOT	49
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	511
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE IFRAME, CLOSED LID	EACH	1
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	825.0
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2
63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4
63100167	TRAFFIC BARRIER TERMINAL, TYPE I(SPECIAL) TANGENT	EACH	4
63100169	TRAFFIC BARRIER TERMINAL, TYPE I(SPECIAL) FLARED	EACH	2
63200310	GUARDRAIL REMOVAL	FOOT	1345
63301210	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	875.0
63302700	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2
63700159	CONCRETE BARRIER, SINGLE FACE, 32 INCH HEIGHT (SPECIAL)	FOOT	256
63800048	GLARE SCREEN BLADES 48"	EACH	76
64000120	SIGHT SCREEN (CHAIN LINK FENCE) 8'	FOOT	605
64200105	SHOULDER RUMBLE STRIP	FOOT	9633
66502400	WOVEN WIRE FENCE TO BE REMOVED AND RE-ERECTED	FOOT	1200
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10
67100100	MOBILIZATION	L SUM	1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	4
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY INTERSTATE MAINTENANCE 90% FEDERAL 10% STATE X031-2A
70101900	TRAFFIC CONTROL AND PROTECTION (DETOUR I)	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	6
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	18
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1636
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	18704
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	14943
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	28
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	15233
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1112.5
78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	7304
78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	28
78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 5"	FOOT	1220
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	105
78200405	GUARDRAIL MARKERS	EACH	27
78200500	BARRIER WALL MARKERS	EACH	7
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	8
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	105
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	56
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	4.0
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	37.4
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2
Z0054530	ROCK FILL - SUBGRADE	TON	6826
XX005953	TEMPORARY CHAIN LINK FENCE, 8'	FOOT	1341
X0321792	TEMPORARY LIGHTING SYSTEM SPECIAL, LOCATION NO.1	L SUM	1
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	407
X0484300	MEDIAN INLET BOX REMOVAL	EACH	2
X2020500	EARTH EXCAVATION (ROCKFILL)	CU YD	3365
X2503000	MAINTENANCE MOWING	ACRE	6.00
X6330103	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE I(SPECIAL, TANGENT	EACH	1
X6330110	RELOCATE TRAFFIC BARRIER TERMINAL, TYPE I(SPECIAL)	EACH	2
X7800620	URETHANE PAVEMENT MARKING - LINE 5"	FOOT	10180

* DENOTES SPECIALTY ITEM

FILE NAME : c:\pwork\p1001\LAUGH\INRL\d0110282\d	USER NAME : laughlinr1	DESIGNED -	REVISED -
quantitiesSummary.dgn		DRAWN -	REVISED -
PLOT SCALE = 40.000 ' / IN.		CHECKED -	REVISED -
PLOT DATE = Dec-03-2008 07:32:46AM		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 2 OF 2 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	68-4B-1 & 111BR	MONTGOMERY	145	5
	FAI 55 & FAS 1769	CONTRACT NO. 72A63		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		