

CORRUGATED MEDIAN REMOVAL	
LOCATION	QUANTITY (SQ FT)
BROADWAY AVE STA 99+33.69 TO STA 99+46.06	52
<b>TOTAL</b>	<b>52</b>

STORM SEWER REMOVAL	
LOCATION	QUANTITY (FOOT)
BROADWAY AVE & 4TH ST S.E. QUADRANT	48
BROADWAY AVE & 5TH ST N.W. QUADRANT	20
S.W. QUADRANT	20
N.E. QUADRANT	42
S.E. QUADRANT	8
<b>TOTAL</b>	<b>138</b>

STORM SEWER, RCCP, TYPE 1, 12"	
LOCATION	QUANTITY (FOOT)
BROADWAY AVE & 4TH ST S.E. QUADRANT	65
BROADWAY AVE & 5TH ST N.W. QUADRANT	18
S.W. QUADRANT	22
N.E. QUADRANT	42
S.E. QUADRANT	16
<b>TOTAL</b>	<b>163</b>

CLASS B PATCHES, TYPE IV, 10 INCH (NOTE: ALL PATCHES PAID FOR AS TYPE II REGARDLESS OF SIZE)	
LOCATION	QUANTITY (SQYD)
BROADWAY AVE & 4TH ST S.E. QUADRANT	7
BROADWAY AVE & 5TH ST N.W. QUADRANT	15
S.W. QUADRANT	22
N.E. QUADRANT	27
S.E. QUADRANT	2
<b>TOTAL</b>	<b>73</b>

DOWEL BARS (NOTE: TO BE INSTALLED IN EXISTING PAVEMENT ALONG ENDS OF PR PATCHES; DOWEL BARS REQUIRED IN PCC JOINTED PAVEMENT ARE NOT INCLUDED IN THIS SCHEDULE, BUT ARE REQUIRED AND ARE NOT PAID FOR SEPARATELY)	
LOCATION	QUANTITY (EACH)
BROADWAY AVE & 4TH ST S.E. QUADRANT	20
BROADWAY AVE & 5TH ST N.W. QUADRANT	34
S.W. QUADRANT	35
N.E. QUADRANT	60
S.E. QUADRANT	4
<b>TOTAL</b>	<b>153</b>

CONTROLLED LOW STRENGTH MATERIAL (FOR TRENCH BACKFILL)	
LOCATION	QUANTITY (CUYD)
BROADWAY AVE & 4TH ST S.E. QUADRANT	25
BROADWAY AVE & 5TH ST N.W. QUADRANT	9
S.W. QUADRANT	10
N.E. QUADRANT	19
S.E. QUADRANT	5
<b>TOTAL</b>	<b>68</b>

COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.12	
LOCATION	QUANTITY (FOOT)
4TH ST S.E. QUADRANT	429
S.W. QUADRANT	23
5TH ST N.W. QUADRANT	31
N.E. QUADRANT	55
S.W. QUADRANT	55
S.E. QUADRANT	42
<b>TOTAL</b>	<b>634</b>

COMBINATION CONCRETE CURB & GUTTER, TYPE M-6.06 (VARIABLE WIDTH GUTTER FLAG)	
LOCATION	QUANTITY (FOOT)
BROADWAY AVE & 4TH ST S.E. QUADRANT ISLAND	76
<b>TOTAL</b>	<b>76</b>

SUBBASE GRANULAR MATERIAL, TYPE A, 4"	
LOCATION	QUANTITY (SQYD)
4TH ST STA 6+16.66 TO STA 7+88.30	96
STA 7+88.30 TO STA 9+63.00	366
5TH ST N.W. QUADRANT	9
S.W. QUADRANT	50
N.E. QUADRANT	36
S.E. QUADRANT	27
BROADWAY AVE STA 99+21.00 TO STA 99+46.06	12
<b>TOTAL</b>	<b>596</b>

CONCRETE MEDIAN, TYPE SM-6.06	
LOCATION	QUANTITY (SQ FT)
BROADWAY AVE STA 99+21.00 TO STA 99+33.69	48
<b>TOTAL</b>	<b>48</b>

SUBBASE GRANULAR MATERIAL, TYPE A	
LOCATION	QUANTITY (TON)
BROADWAY AVE & 4TH ST S.E. QUADRANT ISLAND	23
<b>TOTAL</b>	<b>23</b>

TEMPORARY RAMP	
LOCATION	QUANTITY (SQYD)
4TH ST STA 6+16.66	3
STA 7+88.30	3
Est. Quantity for other locations	65
<b>TOTAL</b>	<b>71</b>

CONCRETE MEDIAN SURFACE, 4 INCH	
LOCATION	QUANTITY (SQ FT)
BROADWAY AVE & 4TH ST S.W. QUADRANT	30
N.E. ISLAND	20
S.E. QUADRANT	220
S.E. ISLAND	25
E. MEDIAN	75
BROADWAY AVE & 5TH ST N.W. QUADRANT	10
S.W. QUADRANT	15
N.E. QUADRANT	30
<b>TOTAL</b>	<b>425</b>

COMBINATION CURB AND GUTTER REMOVAL	
LOCATION	QUANTITY (FOOT)
BROADWAY STA 99+21.00 TO STA 99+33.69	30
BROADWAY AVE & 4TH ST S.W. QUADRANT	28
S.E. QUADRANT	444
BROADWAY AVE & 5TH ST N.W. QUADRANT	31
S.W. QUADRANT	64
N.E. QUADRANT	64
S.E. QUADRANT	47
<b>TOTAL</b>	<b>708</b>

ISLAND REMOVAL	
LOCATION	QUANTITY (SQ FT)
BROADWAY AVE & 4TH ST S.E. QUADRANT	170
<b>TOTAL</b>	<b>170</b>

SIDEWALK REMOVAL	
LOCATION	QUANTITY (SQ FT)
BROADWAY AVE & 4TH ST N.W. QUADRANT	145
S.W. QUADRANT	176
N.E. QUADRANT	66
N.E. ISLAND	52
E. MEDIAN	60
BROADWAY AVE & 5TH ST N.W. QUADRANT	184
S.W. QUADRANT	230
N.E. QUADRANT	340
S.E. QUADRANT	300
<b>TOTAL</b>	<b>1553</b>

CONCRETE MEDIAN SURFACE REMOVAL	
LOCATION	QUANTITY (SQ FT)
BROADWAY STA 99+21.00 TO STA 99+33.69	36
BROADWAY AVE & 4TH ST N.E. ISLAND	32
E. MEDIAN	100
<b>TOTAL</b>	<b>168</b>

PAVEMENT REMOVAL	
LOCATION	QUANTITY (SQ YD)
BROADWAY AVE & 4TH ST S.E. QUADRANT	115
<b>TOTAL</b>	<b>115</b>

PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 10"	
LOCATION	QUANTITY (SQ YD)
BROADWAY STA 99+33.69 TO STA 99+46.06	7
5TH ST S.W. QUADRANT	34
N.E. QUADRANT	20
S.E. QUADRANT	15
<b>TOTAL</b>	<b>76</b>

PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	
LOCATION	QUANTITY (SQ YD)
4TH ST STA 6+16.66 TO STA 7+88.30	48
STA 7+88.30 TO STA 9+63.00	244
<b>TOTAL</b>	<b>292</b>

TIE BARS (NOTE: TO BE INSTALLED IN EXISTING PAVEMENT ALONG PR PCC PAVT / WID; TIE BARS REQUIRED ALONG C & G ARE NOT INCLUDED IN THIS SCHEDULE, BUT ARE REQUIRED AND ARE NOT PAID FOR SEPARATELY)	
LOCATION	QUANTITY (EACH)
BROADWAY STA 99+33.69 TO STA 99+46.06	12
4TH ST STA 6+16.66 TO STA 7+88.30	69
STA 7+88.30 TO STA 9+63.00	80
5TH ST N.W. QUADRANT	13
S.W. QUADRANT	26
N.E. QUADRANT	26
S.E. QUADRANT	19
<b>TOTAL</b>	<b>245</b>

PAVEMENT FABRIC	
LOCATION	QUANTITY (SQ YD)
4TH ST STA 6+16.66 TO STA 7+88.30	48
STA 7+88.30 TO STA 9+63.00	244
<b>TOTAL</b>	<b>292</b>

HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	
LOCATION	QUANTITY (TON)
BROADWAY STA 99+33.69 TO STA 99+46.06	0.8
4TH ST STA 6+16.66 TO STA 7+88.30	5.4
5TH ST S.W. QUADRANT	3.8
N.E. QUADRANT	2.3
S.E. QUADRANT	1.7
<b>TOTAL</b>	<b>14</b>

PCC SIDEWALK, 4 INCH	
LOCATION	QUANTITY (SQ FT)
BROADWAY AVE & 4TH ST N.W. QUADRANT	120
S.W. QUADRANT	155
N.E. QUADRANT	90
N.E. ISLAND	80
S.E. QUADRANT	120
S.E. ISLAND	145
E. MEDIAN	90
BROADWAY AVE & 5TH ST N.W. QUADRANT	170
S.W. QUADRANT	180
N.E. QUADRANT	310
S.E. QUADRANT	170
<b>TOTAL</b>	<b>1630</b>

DETECTABLE WARNINGS	
LOCATION	QUANTITY (SQ FT)
BROADWAY AVE & 4TH ST N.W. QUADRANT	16
S.W. QUADRANT	20
N.E. QUADRANT	12
N.E. ISLAND	36
S.E. QUADRANT	10
S.E. ISLAND	30
E. MEDIAN	20
BROADWAY AVE & 5TH ST N.W. QUADRANT	26
S.W. QUADRANT	14
N.E. QUADRANT	14
S.E. QUADRANT	20
<b>TOTAL</b>	<b>218</b>

PREFORMED PLASTIC PAVEMENT MARKING TYPE B - LINE 24" (SOLID WHITE)	
LOCATION	QUANTITY (FOOT)
STOP BARS AT 4TH & BROADWAY	
RT-TURN LANE ON 4TH ST S.E. QUADRANT	18
4TH ST STA 9+49.00	33
BROADWAY EAST-BOUND, STA 99+66.1	24
BROADWAY WEST-BOUND, STA 100+41.5	23
BROADWAY WEST-BOUND RT TURN LANE, STA 100+47	14
<b>TOTAL</b>	<b>112</b>

PREFORMED PLASTIC PAVEMENT MARKING TYPE B - LETTERS & SYMBOLS (SOLID WHITE)	
LOCATION	QUANTITY (SQ FT)
4TH ST & BROADWAY 3 RIGHT-TURN ARROWS	46.8
3 LEFT-TURN ARROWS	46.8
<b>TOTAL</b>	<b>93.6</b>

PREFORMED PLASTIC PAVEMENT MARKING TYPE B - LINE 5"	
LOCATION	QUANTITY (FOOT)
5" WHITE SKIP-DASH STA 6+16.66 TO STA 9+49	83
<b>TOTAL</b>	<b>83</b>