

PAVEMENT PATCHING

LOCATION	SIDE	SIZE	AREA	PAVEMENT PATCHING		
				TYPE II, 14 IN	TYPE III, 14 IN	TYPE IV, 14 IN
STATION	(EB/WB)	L x W	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)
141+85	EB	6' x 11'	7.3	7.3		
142+10	EB	6' x 11'	7.3	7.3		
144+10	EB	6' x 11'	7.3	7.3		
145+20	EB	6' x 11'	7.3	7.3		
146+05	EB	6' x 11'	7.3	7.3		
147+05	EB	10' x 11'	12.2	12.2		
148+45	EB	6' x 11'	7.3	7.3		
163+50	EB	6' x 11'	7.3	7.3		
165+50	EB	6' x 11'	7.3	7.3		
175+50	EB	10' x 11'	12.2	12.2		
177+50	EB	6' x 11'	7.3	7.3		
179+56	EB	8' x 11'	9.8	9.8		
182+31	EB	6' x 11'	7.3	7.3		
185+20	EB	100' x 4'	44.4			44.4
192+15	EB	6' x 11'	7.3	7.3		
196+75	EB	10' x 11'	12.2	12.2		
218+75	EB	6' x 11'	7.3	7.3		
222+75	EB	10' x 4'	4.4	4.4		
228+30	EB	50' x 4'	22.2		22.2	
239+80	EB	10' x 11'	12.2	12.2		
248+95	EB	6' x 11'	7.3	7.3		
250+15	EB	6' x 11'	7.3	7.3		
255+72	EB	6' x 11'	7.3	7.3		
258+10	EB	300' x 4'	133.3			133.3
260+35	EB	6' x 11'	7.3	7.3		
261+00	EB	6' x 11'	7.3	7.3		
261+52	EB	6' x 11'	7.3	7.3		
262+05	EB	6' x 11'	7.3	7.3		
275+00	EB	100' x 4'	44.4			44.4
275+50	EB	50' x 4'	22.2		22.2	
281+59	EB	50' x 4'	22.2		22.2	
287+25	EB	6' x 11'	7.3	7.3		
301+25	EB	6' x 11'	7.3	7.3		
302+51	EB	6' x 11'	7.3	7.3		
307+58	EB	8' x 11'	9.8	9.8		
317+45	EB	6' x 11'	7.3	7.3		
319+86	EB	110' x 4'	48.9			48.9
322+25	EB	6' x 11'	7.3	7.3		
329+25	EB	6' x 11'	7.3	7.3		
353+45	EB	10' x 11'	12.2	12.2		
355+56	EB	6' x 11'	7.3	7.3		
360+00	EB	6' x 11'	7.3	7.3		
361+50	EB	10' x 11'	12.2	12.2		
365+75	EB	10' x 11'	12.2	12.2		
158+95	WB	100' x 4'	44.4			44.4

CONT.

PAVEMENT PATCHING (CONT)

160+05	WB	8' x 11'	9.8	9.8		
167+85	WB	6' x 11'	7.3	7.3		
170+35	WB	200' x 4'	88.9			88.9
185+54	WB	200' x 4'	88.9			88.9
236+25	WB	6' x 11'	7.3	7.3		
238+51	WB	8' x 11'	9.8	9.8		
239+45	WB	6' x 11'	7.3	7.3		
246+58	WB	6' x 11'	7.3	7.3		
255+01	WB	150' x 4'	66.7			66.7
257+84	WB	150' x 4'	66.7			66.7
259+65	WB	20' x 11'	24.4		24.4	
261+55	WB	50' x 4'	22.2		22.2	
262+10	WB	6' x 11'	7.3	7.3		
262+25	WB	6' x 11'	7.3	7.3		
262+45	WB	6' x 11'	7.3	7.3		
263+00	WB	150' x 4'	66.7			66.7
265+00	WB	6' x 11'	7.3	7.3		
266+00	WB	6' x 11'	7.3	7.3		
272+00	WB	10' x 11'	12.2	12.2		
273+80	WB	6' x 11'	7.3	7.3		
275+58	WB	40' x 4'	17.8		17.8	
278+51	WB	100' x 4'	44.4			44.4
283+20	WB	60' x 4'	26.7			26.7
284+80	WB	20' x 11'	24.4		24.4	
290+00	WB	6' x 11'	7.3	7.3		
302+50	WB	6' x 11'	7.3	7.3		
305+25	WB	6' x 11'	7.3	7.3		
312+50	WB	6' x 11'	7.3	7.3		
315+45	WB	10' x 11'	12.2	12.2		
316+80	WB	6' x 11'	7.3	7.3		
320+80	WB	6' x 11'	7.3	7.3		
322+50	WB	6' x 11'	7.3	7.3		
323+45	WB	10' x 11'	12.2	12.2		
328+45	WB	6' x 11'	7.3	7.3		
332+40	WB	6' x 11'	7.3	7.3		
336+45	WB	8' x 11'	9.8	9.8		
341+56	WB	100' x 4'	44.4			44.4
352+40	WB	6' x 11'	7.3	7.3		
358+56	WB	8' x 11'	9.8	9.8		
360+45	WB	10' x 11'	12.2	12.2		
361+20	WB	10' x 11'	12.2	12.2		
363+50	WB	10' x 11'	12.2	12.2		
366+75	WB	10' x 11'	12.2	12.2		
ANTICIPATED FAILURES 25% =				144.3	38.9	202.2
TOTAL =				721.4	194.3	1011.0

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	(133,134)RS-4,135RS-5	ST. CLAIR, MONROE	252	7
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

PLOT DATE = #DATE#  
 FILE NAME = #FILE#  
 PLOT SCALE = #SCALE#  
 REFERENCE = #REF#

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**PAVEMENT PATCHING SCHEDULE**  
 FAP ROUTE 809 (IL 158)  
 SECTION (133,134)RS-4,135RS-5  
 MONROE & ST. CLAIR COUNTIES  
 SCALE: VERT. \_\_\_\_\_ DRAWN BY \_\_\_\_\_  
 DATE: \_\_\_\_\_ CHECKED BY \_\_\_\_\_