

SUMMARY OF QUANTITIES

ST. CLAIR COUNTY

ST. CLAIR CO. CLINTON CO.

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE										-----	-----	-----
CODE NO	ITEM	UNIT		1000-2A ST. CLAIR CO. 90% FED 10% STATE	1000-2A CLINTON CO. 90% FED 10% STATE	X231-2A 082-0190 90% FED 10% STATE	X231-2A 082-0191 90% FED 10% STATE	X231-2A 014-0038 90% FED 10% STATE	X231-2A 082-0192 90% FED 10% STATE	X231-2A 082-0193 90% FED 10% STATE	X131-2A 082-0194 90% FED 10% STATE	X131-2A 082-0195 90% FED 10% STATE				
X0320887	POLYMER CONCRETE	CU FT	33.1			1.9	12.5	10.9				7.8				
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	472			472										
X0712400	TEMPORARY PAVEMENT	SQ YD	36	36												
X4066580	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	27789	26594	1195											
X7010825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701423 (SPECIAL)	L SUM	1	1												
XX003503	FLARED END SECTION REMOVAL	EACH	1	1												
XZ030260	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	11			2	2	2	2	2	2	2				
XZ193500	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 1/4"	SQ YD	1829				976	853								
Z0002005	ATTENUATOR BASE	SQ YD	16	8	8											
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SQ YD	1829				976	853								
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	1			1										
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	86			63			8	2		13				
Z0017202	DOWEL BARS 1 1/2"	EACH	784	784												
Z0027200	FURNISHING AND SETTING WOOD POSTS	EACH	8	8												
Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	2	1	1											
Z0030150	IMPACT ATTENUATORS, (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	1	1											
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	10			2	2	2	1	1	1	1				
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	10			2	2	2	1	1	1	1				
Z0053750	RETROFIT CONCRETE PARAPET	FOOT	1435			470	467	498								
Z0075340	TIE BARS 1 3/8"	EACH	40	40												
X0321159	MEDIAN INLET, SPECIAL	EACH	2	2												

Rev. *ST. CLAIR & CLINTON

FILE NAME =	USER NAME = conoverpj	DESIGNED - ----	REVISED - ----	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ci:\pwwork\pwwid\conoverpj\dms58410\pl	00505b.dgn	DRAWN - ----	REVISED - ----		64	82-(8,9,10)RS-3	•	78	6			
	PLOT SCALE = 50,0000' / IN.	CHECKED - ----	REVISED - ----		SCALE: ----- SHEET NO. 4 OF 4 SHEETS STA. ----- TO STA. -----			CONTRACT NO. 76855				
	PLOT DATE = 12/11/2008	DATE - ----	REVISED - ----		FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT							