

REMOVAL SCHEDULE

STATION				PVMT REMOVAL (SQ YD)	DRIVEWAY PVMT REMOVAL (SQ YD)	HMA SURFACE REMOVAL VAR. DEPTH (SQ YD)	PIPE CULVERT REMOVAL (FT)	SPBGR (FT)
1112+25.00	TO	1117+81.50	RT					
1112+75.00	TO	1115+74.14	RT/LT			797.71		
1113+09.75		PE	LT				30.00	
1114+22.76		PE	LT		30.08		31.50	
1114+77.66		PE	RT				70.00	
1114+98.40		PE	LT				53.50	
1116+04.24	TO	1117+81.50	RT					177.26
1116+17.72	TO	1117+81.50	LT					163.78
1116+92.50	TO	1117+81.50	RT/LT	260.29				
1120+28.95	TO	1121+17.50	RT/LT	258.70				
1120+28.95	TO	1121+68.60	LT					139.65
1120+28.95	TO	1121+93.50	RT					164.55
1124+20.00	TO	1124+75.00	RT/LT			146.67		
TOTAL				518.98	30.08	944.37	185.00	645.24

TREE REMOVAL SCHEDULE

STATION	OFFSET	RT/LT	6 TO 15 UNITS			OVER 15 UNITS			
1117+32.88	40.1	RT	6						
1117+50.44	40.7	RT	10						
1117+51.10	30.0	LT				27			
1117+57.67	39.5	RT	10						
1117+68.98	42.2	LT					33		
1117+77.25	43.2	RT			14				
1119+36.64	35.9	RT				22			
1119+58.84	42.4	RT						40	
SUB-TOTAL			6	20	14	22	27	33	40
TOTAL			40			122			

EARTHWORK SCHEDULE

LOCATION		EARTH EXCAVATION (CU YD)	EARTH EXCAVATION ADJTD FOR SHRINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
STA 1112+68.50	TO STA 1117+28.50	190.0	142.5	102.5	40.0
STA 1120+81.50	TO STA 1125+00.00	31.9	23.9	688.7	-664.8
TOTAL		221.9	166.4	791.2	-624.8

EARTHWORK SCHEDULE (WIDENING)

LOCATION		EARTH EXCAVATION (CU YD)	EARTH EXCAVATION ADJTD FOR SHRINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
STA 1112+75.00	TO STA 1117+81.50	35.2	26.4	0.0	26.4
STA 1120+28.95	TO STA 1125+25.00	44.0	33.0	0.0	33.0
TOTAL		79.2	59.4	0.0	59.4

RIGHT-OF-WAY MARKERS SCHEDULE

LOCATION			ROW MARKERS (EA)
STATION	RT/LT	OFFSET	
1112+86.39	RT	40	1
1113+00.00	RT	55	1
1113+20.61	LT	45	1
1113+50.00	RT	55	1
1113+58.78	RT	53.24	1
1114+00.00	RT	45	1
1114+52.29	LT	45	1
1119+05.00	RT	45	1
1119+05.00	RT	50	1
1120+00.00	RT	50	1
1120+02.88	RT	50.29	1
1120+43.26	LT	45	1
1120+50.00	RT	55	1
1120+68.68	LT	105	1
1122+40.23	LT	105	1
1122+40.23	LT	50	1
1123+00.00	RT	55	1
1123+50.00	RT	50	1
1125+00.00	LT	50	1
1125+00.00	RT	50	1
1125+50.00	LT	40	1
1125+50.00	RT	40	1
TOTAL			22

ROW & PROPERTY CORNERS SCHEDULE

LOCATION			ROW PROPERTY CORNERS (EA)
STATION	RT/LT	OFFSET	
1112+86.39	RT	40	1
1114+52.29	LT	45	1
1115+28.78	RT	45	1
1119+05.00	RT	50	1
TOTAL			4

CHANNEL EXCAVATION SCHEDULE

LOCATION		EARTH EXCAVATION (CU YD)	EARTH EXCAVATION ADJTD FOR SHRINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
STA 1117+28.50	TO STA 1118+65.00	1973.9	1480.4	0.0	1480.4
STA 1119+55.40	TO STA 1120+81.50	1461.8	1096.4	22.5	1073.9
TOTAL		3435.7	2576.8	22.5	2554.3

SEEDING SCHEDULE

STA	STA	SEEDING CLASS 2 (ACRE)	NITROGEN FERT. NUTR (POUND)	PHOSPHORUS FERT. NUTR (POUND)	POTASSIUM FERT. NUTR (POUND)	MULCH METHOD 1 (ACRE)
1112+61.50	TO 1119+05.00	LT 0.31	27.75	27.75	27.75	0.31
1120+78.88	TO 1125+50.00	LT 0.39	35.03	35.03	35.03	0.39
1112+61.50	TO 1119+05.00	RT 0.41	36.64	36.64	36.64	0.41
1120+78.88	TO 1125+50.00	RT 0.40	35.77	35.77	35.77	0.40
TOTAL		1.51	135.18	135.18	135.18	* 1.51

\* NOT A TOTAL QUANTITY (SEE TEMPORARY EROSION CONTROL SCHEDULE ON SHEET 22)