



TEMPORARY EROSION CONTROL SCHEDULE

LOCATION	RT/LT	TEMPORARY EROSION CONTROL SEEDING (POUND)	MULCH METHOD 1 (ACRE)	PERIMETER EROSION BARRIER (FOOT)	TEMP. DITCH CHECK (EACH)	INLET & PIPE PROTECTION (EACH)
1112+61.50 TO 1125+60.00	LT	125.56	1.40			
1112+61.50 TO 1125+60.00	RT	144.82	1.61			
1113+09.75	PE LT					1
1113+25.00	RT				1	
1113+65.00	LT				1	
1114+22.76	PE LT					1
1114+25.00	RT				1	
1114+77.66	PE RT					1
1114+98.40	PE LT					1
1115+50.00 TO 1117+00.00	RT			151.5		
1115+75.00	LT				1	
1116+75.00	LT				1	
1120+75.00 TO 1121+93.16	LT			119.5		
1120+75.00 TO 1125+28.00	RT			456.0		
1122+03.00 TO 1125+52.75	LT			355.0		
TOTAL		270.38	*3.01	1082.0	5	4

NOTE: QUANTITIES FOR TEMP. EROSION CONTROL SEEDING AND MULCH METHOD 1 ARE FOR STAGE 1 & 2.

*NOT A TOTAL QUANTITY (SEE SEEDING SCHEDULE ON SHEET 8)