

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		90% FED 10% STATE SFTY-4A	-----	-----	CODE NO	ITEM		UNIT	-----	-----
20200100	EARTH EXCAVATION	CU YD	2150	2150								
25000210	SEEDING, CLASS 2A	ACRE	5.25	5.25								
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	472	472								
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	472	472								
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	472	472								
25100105	MULCH, METHOD 1	ACRE	5.25	5.25								
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	525	525								
28000500	INLET AND PIPE PROTECTION	EACH	28	28								
28000700	MULCH, METHOD 1	ACRE	5.25	5.25								
48203013	HOT-MIX ASPHALT SHOULDERS, 4"	SQ YD	19349	19349								
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3								
67100100	MOBILIZATION	L SUM	1	1								
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1								
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5								
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	12	12								
80300100	LOCATING UNDERGROUND CABLE	FOOT	100	100								
X0325589	HIGH TENSION CABLE MEDIAN BARRIER	FOOT	27923	27923								
X0325590	HIGH TENSION CABLE MEDIAN BARRIER TERMINAL	EACH	12	12								