

PAVEMENT AND SHOULDER SCHEDULE

LOCATION STATION TO STATION	TYPICAL NUMBER	HOT-MIX ASPHALT LEVELING BINDER TON	HOT-MIX ASPHALT SURFACE COURSE TON	PRIME COAT*		AGGREGATE SHOULDERS, TYPE B TONS	HOT-MIX ASPHALT SURFACE REMOVAL, 1" SO YD	HOT-MIX ASPHALT SURFACE REMOVAL, 1-1/2" SO YD	HOT-MIX ASPHALT SURFACE REMOVAL, 2-1/4" SO YD	HOT-MIX ASPHALT SURFACE REMOVAL BUTT JOINT* SO YD	TEMPORARY RAMP* SO YD	AGGREGATE BASE COURSE TYPE B-8" SO YD
				BITUMINOUS MATERIALS GAL	AGGREGATE TON							
RURAL SECTION												
+60.0 TO 74+16.0	1	892.7	1793.9	2762.6	63.8	907.6	21250.7			72.2	14.4	
74+16.0 TO 75+24.0	1	13.1	26.3	40.6	0.9	13.3	312.0					
75+24.0 TO 163+35.9	1	1069.3	2149.0	3309.4	76.4	1087.2	25456.6					
163+35.9 TO 163+39.7	STA EQN											
163+39.7 TO 174+00.0	1	128.7	258.6	398.2	9.2	130.8	3063.1			28.9		
174+00.0 TO 174+35.3	2	4.0	7.9	12.2	0.1			94.1				
174+35.3 TO 174+53.5	STA EQN											
174+53.5 TO 188+90.0	2	160.9	321.8	498.0	5.7			3830.7				
188+90.0 TO 193+82.0	1	59.7	120.0	184.8	4.3	60.7	1421.3			72.2	14.4	
193+82.0 TO 194+24.0	GAP 097-2007											
194+24.0 TO 238+92.8	1	542.3	1089.8	1678.3	38.7	551.4	12909.9			43.3	14.4	
238+92.8 TO 238+95.9	STA EQN											
238+95.9 TO 277+14.2	1	463.4	931.2	1434.0	33.1	471.1	11030.6					
277+14.2 TO 277+69.1	STA EQN											
277+69.1 TO 303+08.5	1	308.2	619.3	953.7	22.0	313.3	7336.0					
303+08.5 TO 304+13.3	STA EQN											
304+13.3 TO 355+00.0	1	617.3	1240.5	1910.3	44.1	627.6	14694.9					
ENTRANCE AND SIDEROAD TOTALS				229.0	2.0					501.0		545.0
RURAL SECTION TOTALS		4260	8559	13411	301	4164	97476	3925		718	44	545
URBAN SECTION												
355+00.0 TO 373+00.0	3	218.4	439.0	676.0	15.6				5200.0	72.2		
373+00.0 TO 378+40.0	4	63.0	126.0	195.0	2.3				1500.0			
378+40.0 TO 381+90.0	5	55.5	111.1	171.9	2.0				1322.2		26.4	
URBAN SECTION TOTALS		337	677	1043	20				8023	73	27	
TOTALS		4597	9236	14454	321	4164	97476	3925	8023	791	71	545

*SEE SIDEROAD AND ENTRANCE SCHEDULE FOR ADDITIONAL QUANTITIES.