

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
815	D9 CM BRIDGE REPAIR FY 09-1	WHITE	16	3
FED. ROAD DIST. NO. 7	ILLINOIS	CONTRACT NO. 78094		

CODE NO.	CONSTRUCTION TYPE CODE: SFTY-2A ITEM DESCRIPTION	100% STATE	
		UNIT	TOTAL QUANTITY
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	5
40600300	AGGREGATE (PRIME COAT)	TON	1
44001005	HOT-MIX ASPHALT SURFACE REMOVAL	SQ YD	835.3
40600990	TEMPORARY RAMP	SQ YD	57
40603320	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N90	TON	93
50102400	CONCRETE REMOVAL	CU YD	8.1
50300255	CONCRETE SUPERSTRUCTURE	CU YD	7.9
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	1690
50800515	BAR SPLICERS	EACH	14
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	10
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1030
52000110	PREFORMED JOINT STRIP SEAL	FOOT	65
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	10
52100520	ANCHOR BOLTS, 1"	EACH	20
59000200	EPOXY CRACK INJECTION	FOOT	57.5
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	803
63304385	TRAFFIC BARRIER TERMINAL REMOVAL, TYPE 1	EACH	1
67100100	MOBILIZATION	L SUM	1
70100100	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316	EACH	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	96.4