

SCHEDULES

FAU RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
S154	04-00343-00-BR	WINNEBAGO	92	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

THERMOPLASTIC PAVEMENT MARKING -

LINE 6"

STATION	FOOT	REMARKS
L 123+35.60 - 135+00	1,164	L OF C/L NPZ (YELLOW)
L 138+10 - 146+10	200	L OF C/L 10/30 SKIP DASH (YELLOW)
L 146+10 - 152+60	650	L OF C/L NPZ (YELLOW)
L 153+60 - 154+37	77	L OF C/L NPZ (YELLOW)
R 123+35.60 - 125+50	214	R OF C/L NPZ (YELLOW)
R 125+50 - 137+10	290	R OF C/L 10/30 SKIP DASH (YELLOW)
R 138+10 - 152+60	1,450	R OF C/L NPZ (YELLOW)
R 153+60 - 154+37	77	R OF C/L NPZ (YELLOW)
L 123+35.60 - 137+10.12	1,375	LEFT EDGE (WHITE)
L 137+10.12 - 137+50.63	78	LEFT EDGE - RAD. (WHITE)
L 137+67.79 - 138+08.12	78	LEFT EDGE - RAD. (WHITE)
L 138+08.12 - 152+39.16	1,431	LEFT EDGE (WHITE)
L 152+39.16 - 152+89.16	94	LEFT EDGE - RAD. (WHITE)
L 153+10.81 - 153+65.91	99	LEFT EDGE - RAD. (WHITE)
L 153+65.91 - 154+37.00	71	LEFT EDGE (WHITE)
R 123+35.60 - 137+06.04	1,370	RIGHT EDGE (WHITE)
R 137+06.04 - 137+47.16	78	RIGHT EDGE - RAD. (WHITE)
R 137+70.04 - 138+10.04	78	RIGHT EDGE - RAD. (WHITE)
R 138+10.04 - 154+37.00	1,627	RIGHT EDGE (WHITE)
PROJECT TOTAL	10,502	

78000400

TERMINAL MARKER - DIRECT APPLIED

STATION	EACH	REMARKS
L 125+39.21	1	
L 135+36.20	1	
L 139+78.26	1	
L 151+63.93	1	
R 123+91.81	1	
R 134+26.28	1	
R 144+09.57	1	
R 151+63.99	1	
PROJECT TOTAL	8	

78201000

GUARDRAIL MARKERS, TYPE A

STATION	EACH	REMARKS
L 125+74.64	1	FACES NORTHWEST BOUND TRAFFIC
L 126+54.64	1	FACES NORTHWEST BOUND TRAFFIC
L 127+34.64	1	FACES NORTHWEST BOUND TRAFFIC
L 132+63.27	1	FACES NORTHWEST BOUND TRAFFIC
L 133+43.27	1	FACES NORTHWEST BOUND TRAFFIC
L 134+23.27	1	FACES NORTHWEST BOUND TRAFFIC
L 135+03.27	1	FACES NORTHWEST BOUND TRAFFIC
L 135+83.27	1	FACES NORTHWEST BOUND TRAFFIC
L 136+63.27	1	FACES NORTHWEST BOUND TRAFFIC
L 138+84.97	1	FACES NORTHWEST BOUND TRAFFIC
L 139+64.97	1	FACES NORTHWEST BOUND TRAFFIC
L 140+44.97	1	FACES NORTHWEST BOUND TRAFFIC
L 141+24.97	1	FACES NORTHWEST BOUND TRAFFIC
L 142+04.97	1	FACES NORTHWEST BOUND TRAFFIC
L 146+04.97	1	FACES NORTHWEST BOUND TRAFFIC
L 149+48.47	1	FACES NORTHWEST BOUND TRAFFIC
L 150+28.47	1	FACES NORTHWEST BOUND TRAFFIC
L 151+08.47	1	FACES NORTHWEST BOUND TRAFFIC
L 151+88.47	1	FACES NORTHWEST BOUND TRAFFIC
R 124+39.73	1	FACES SOUTHEAST BOUND TRAFFIC
R 125+19.73	1	FACES SOUTHEAST BOUND TRAFFIC
R 125+99.73	1	FACES SOUTHEAST BOUND TRAFFIC
R 126+79.73	1	FACES SOUTHEAST BOUND TRAFFIC
R 132+43.36	1	FACES SOUTHEAST BOUND TRAFFIC
R 133+23.36	1	FACES SOUTHEAST BOUND TRAFFIC
R 134+03.36	1	FACES SOUTHEAST BOUND TRAFFIC
R 138+60.03	1	FACES SOUTHEAST BOUND TRAFFIC
R 139+40.03	1	FACES SOUTHEAST BOUND TRAFFIC
R 140+20.03	1	FACES SOUTHEAST BOUND TRAFFIC
R 141+00.03	1	FACES SOUTHEAST BOUND TRAFFIC
R 141+80.03	1	FACES SOUTHEAST BOUND TRAFFIC
R 145+80.03	1	FACES SOUTHEAST BOUND TRAFFIC
R 151+43.53	1	FACES SOUTHEAST BOUND TRAFFIC
R 152+23.53	1	FACES SOUTHEAST BOUND TRAFFIC
R 153+03.53	1	FACES SOUTHEAST BOUND TRAFFIC
R 153+83.53	1	FACES SOUTHEAST BOUND TRAFFIC
R 154+63.53	1	FACES SOUTHEAST BOUND TRAFFIC
PROJECT TOTAL	37	

78200410*

GUARDRAIL MARKERS, TYPE B

STATION	EACH	REMARKS
L 128+29	1	FACES NORTHWEST BOUND TRAFFIC
L 129+09	1	FACES NORTHWEST BOUND TRAFFIC
L 129+89	1	FACES NORTHWEST BOUND TRAFFIC
L 130+69	1	FACES NORTHWEST BOUND TRAFFIC
L 131+49	1	FACES NORTHWEST BOUND TRAFFIC
L 147+08.47	1	FACES NORTHWEST BOUND TRAFFIC
L 147+88.47	1	FACES NORTHWEST BOUND TRAFFIC
L 148+68.47	1	FACES NORTHWEST BOUND TRAFFIC
L 149+48.47	1	FACES NORTHWEST BOUND TRAFFIC
R 128+29	1	FACES SOUTHEAST BOUND TRAFFIC
R 129+09	1	FACES SOUTHEAST BOUND TRAFFIC
R 129+89	1	FACES SOUTHEAST BOUND TRAFFIC
R 130+69	1	FACES SOUTHEAST BOUND TRAFFIC
R 131+49	1	FACES SOUTHEAST BOUND TRAFFIC
R 147+08.47	1	FACES SOUTHEAST BOUND TRAFFIC
R 147+88.47	1	FACES SOUTHEAST BOUND TRAFFIC
R 148+68.47	1	FACES SOUTHEAST BOUND TRAFFIC
R 149+48.47	1	FACES SOUTHEAST BOUND TRAFFIC
PROJECT TOTAL	18	

78200420*

TREE, ACER PLATANOIDES CRIMSON KING (CRIMSON KING NORWAY MAPLE), 1-1/4" CALIPER, BALLED AND BURLAPPED

STATION	EACH	REMARKS
AS DIRECTED BY ENGINEER	3	
PROJECT TOTAL	3	

A2000810*

TREE, ACER SACCHARUM (SUGAR MAPLE) 1-1/4" CALIPER, BALLED AND BURLAPPED

STATION	EACH	REMARKS
AS DIRECTED BY ENGINEER	8	
PROJECT TOTAL	8	

A2001710*